

Validate		Print		Help		Percentage BoQ	
Tender Inviting Authority: Project Engineer (civil),CCL, Kathara							
Name of Work:Cleaning of water storage tanks including carriage of Alum and bleaching at New and old filter plant Jarangdih (for a period of two years) under Jarangdih colliery,Kathara Area							
		Category of Services (To Be Selected by Department)		Category of Bidder(To Be Selected by Bidder)		To Be Entered by Department	
ITC Not Available		Works Contract		Bidder's Status (Mandatory)		Rate of GST (in %)	
Name of the Bidder/ Bidding Firm / Company :				Select		18.00	
						0.00	
						0.00	
PRICE SCHEDULE							
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #	
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT in Words	
1	2	3	4	5	6	7	
1	Item Description/ Heading						
2	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and for all lift, as directed by Engineer-in-charge. All kinds of soil	2135.44	cum	139.70	298320.97	INR Two Lakh Ninety Eight Thousand Three Hundred & Twenty and Paise Ninety Seven Only	
3	Carriage of materials By Mechanical Transport including loading,unloading and stacking Earth Lead - 5 km	1067.72	cum	224.10	239276.05	INR Two Lakh Thirty Nine Thousand Two Hundred & Seventy Six and Paise Five Only	
4	Carriage of materials By Mechanical Transport including loading,unloading and stacking Lime, moorum, building rubbish Lead - 5 km	51.00	cum	179.25	9141.75	INR Nine Thousand One Hundred & Forty One and Paise Seventy Five Only	
5	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared.	16200.000	sqm	10.55	170910.00	INR One Lakh Seventy Thousand Nine Hundred & Ten Only	
6	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only	
Total in Figures						717648.77 INR Seven Lakh Seventeen Thousand Six Hundred & Forty Eight and Paise Seventy Seven Only	
Quoted Rate in Figures				Select		0.00 INR Zero Only	
Quoted Rate in Words		INR Zero Only					

