

Tender Inviting Authority:	SO(E&M)/H					
Name of the Work / Contract No:	Maintenance/repairing of 33KV/3.3KV/440V OH line from Basantpur substation to Parej substation, panj substation to mines and colony for monsoon preparation at PEOCP under Hazaribag Area					
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST (in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder / Bidding Firm / Company :		Select	18	0.00	0.00	0.00

PRICE SCHEDULE
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE in Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT in Words
1	2	3	4	5	6	7	8
1	Supplying of two lengths of channel iron 100 mm X 50 mm X 6 mm (9.56 kg per metre) double pole cross arm for three wire 33 KV over head line conductors complete with through bolts and nuts for clamping to the poles, 50 mm X 6 mm M.S. flats welded on one side to the channel iron and with bolts and nuts on the other side for tying the cross arms together, including drilling holes for insulator pins/ fittings, bolts, nuts, washers etc and painting with primer and finish paint as required .	5	Set			0.00	INR Zero Only
2	Supplying and erection of a set of three 11 KV disc insulator for 33 KV over head lines with galvanised insulator fittings, ball and socket type and complete with galvanised strain clamps, bolts, nuts, washers etc. as required.	18	Set			0.00	INR Zero Only
3	Supplying and erection of 33 KV pin insulator complete with large steel head G.I. pin, nuts, washers etc. as required.	20	Set			0.00	INR Zero Only
4	Erection of ACSR conductor of 7/3.35 mm to 7/4.00 diameter and above including binding etc. as required.	400	Kg			0.00	INR Zero Only
5	Supplying and erection of galvanised stay set for 33 KV over head lines complete with 19/ 20 mm dia X 1.8 metres long stay rod, anchor plate of size 45 cm X 45 cm X 7.5 mm thick, thimble, stay clamps, turn buckle (20 mm X 600 mm), 7/ 4.00 mm dia G.I. stay wire and 33 KV strain insulator etc in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required.	10	Set			0.00	INR Zero Only
6	Erection of cradle guard as required.	6	Each			0.00	INR Zero Only
7	Cradle guard making	6	No			0.00	INR Zero Only
8	Tree trimming including cutting of branches and uprooting creeper near/above 33kv outgoing /incoming OH power line	8	KM			0.00	INR Zero Only
9	Erection of ACSR conductor of 7/3.35 mm to 7/4.00 diameter and above including binding etc. as required.	250	Kg			0.00	INR Zero Only
10	Supplying and erection of 11 KV pin insulator complete with largesteel head G.I. pin, nuts, washers etc. as required.	20	No			0.00	INR Zero Only
11	Supplying and erection of 11 KV disc insulator for 11 KV overhead lines with galvanised insulator fittings, ball and socket type and complete with galvanised strain clamps, bolts, nuts, washers etc. as required.	15	No			0.00	INR Zero Only
12	Supplying and erection of bow stay set complete (galvanised)with 19/20 mm dia X 1.8 metres long stay rod, anchor plate of size 45 cm X 45 cm X 7.5 mm, thimble, stay clamps, turn buckle(20 mm X 60 cm), 7/ 4.00 mm dia G.I. stay wire and strain insulator etc in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundationincluding excavation and refilling and also with 0.6 m long braceof size 50 mm X 50 mm X 6 mm angle iron with 50 mm dia pulleyfixed at one end of the brace as required.	8	Set			0.00	INR Zero Only
13	Supplying of two lengths of channel iron 75 mm X 40 mm X 6 mm(7.14 kg per metre) double pole cross arm for three wire 11KVover head line conductors complete with through bolts and nuts for clamping to the poles, 50 mm X 6 mm M.S. flats welded on one side to the channel iron and with bolts and nuts on the otherside for tying the cross arms together, including drilling holes forinsulator pins/ fittings, bolts, nuts and washers etc (as per drawing)and painting with primer and finish paint as required.	2	No			0.00	INR Zero Only
14	Erection of cradle guard as required.	6	Each			0.00	INR Zero Only
15	Cradle guard making	6	No			0.00	INR Zero Only
16	Supplying and erection of galvanised 'D' iron clamps completewith shackle insulator (100 mm X 110 mm), G.I. bolts, nuts andwashers, coach screws etc. as required.	15	Set			0.00	INR Zero Only
17	Erection of all aluminium conductor of 7/1.96 mm to 7/3.10 mm diameter including binding etc. as required.	300	Kg			0.00	INR Zero Only
18	Supplying of two lengths of channel iron 75 mm X 40 mm X 6 mm(7.14 kg per metre) double pole cross arm for three wire 11KVover head line conductors complete with through bolts and nuts for clamping to the poles, 50 mm X 6 mm M.S. flats welded onone side to the channel iron and with bolts and nuts on the otherside for tying the cross arms together, including drilling holes forinsulator pins/ fittings, bolts, nuts and washers etc (as per drawing)and painting with primer and finish paint as required.	2	No			0.00	INR Zero Only
19	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg permetre) cross arm for 4 wire over head line complete with clamps,bolts, nuts and washer etc including drilling of holes for insulatorpins etc (as per drawing) and painting with primer and finishedpaint as required .	1	No			0.00	INR Zero Only
20	Erection of pole of following length in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size) foundation including excavation and refilling etc. as required.Above 10.00 metre and upto 12.00 metre	2	No			0.00	INR Zero Only
21	Supplying and erection of 100 mm X 80 mm pin insulator completewith G. I. Spindle and nuts etc. as required .	30	No			0.00	INR Zero Only
22	Supplying and erection of bow stay set complete (galvanised) with 19/20 mm dia X 1.8 metres long stay rod, anchor plate of size 45 cm X 45 cm X 7.5 mm, thimble, stay clamps, turn buckle (20 mm X 60 cm), 7/ 3.15 mm dia G.I. stay wire and strain insulator etc in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling and also with 0.6 m long brace of size 50 mm X 50 mm X 6 mm angle iron with 50 mm dia pulley fixed at one end of the brace as required.	6	Set			0.00	INR Zero Only
23	Tree trimming including cutting of branches and uprooting creeper near/above 33kv outgoing /incoming OH power line	0.5	KM			0.00	INR Zero Only
24	Total impact of GST for the purpose of CTC	1.00	Nos			0.00	INR Zero Only
Total In Figures						0.00	INR Zero Only
Quoted Rate in Words							INR Zero Only