

Tender Inviting Authority:	SO(E&M)/ H
Name of the Work / Contract No:	Maintenance of 11 KV grade OH Line, 3.3 KV grade OH line and partial tree branches trimming for monsoon preparation at Tapin North OCP under Hazaribagh Area

	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00

PRICE SCHEDULE
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Erection of ACSR conductor of 7/3.35 mm to 7/4 diameter and above including binding etc as reqd.	913.1	Kg			0.00	INR Zero Only
2	Erection of all aluminium conductor of 7/3.40 mm to 7/4.00 diameter and above including binding etc as reqd.	632.68	Kg			0.00	INR Zero Only
3	Supplying and erection of 11 KV pin insulator complete with large steel head GI pin, nuts,washers etc. as required.	57	Set			0.00	INR Zero Only
4	Supplying and erection of 11 KV disc insulator for 11 KV over head lines with galvanised insulator fittings, ball and socket type and complete with galvanised strain clamps, bolts, nuts, washers etc. as required.	39	Set			0.00	INR Zero Only
5	Supply and Erection of stay set complete (Galvanized) with 19/20 mm dia X1.8 m long stay rod, anchor plate of size 45cmX45cmX7.5mm, thimble, stay clap, turn buckle (20 mm x 60 cm), 7/4.00mm dia GI stay wire & strain insulator etc in cement concrete 1:3:6 (1 cement:3coarse sand:6 graded stone aggregate 40 mm nominal size) foundation including excavation & refilling etc as required.	19	Each			0.00	INR Zero Only
6	Dismantling of over head lines comprising of copper/ aluminum over head conductor, G.I wire, cross arms, insulators etc. as required.	1545.78	Kg			0.00	INR Zero Only
7	Erection of cradle guard as required.	16	Each			0.00	INR Zero Only
8	Cradle guard making	16	No			0.00	INR Zero Only
9	Tree trimming including cutting of branches and uprooting creeper near/above 11kv/3.3 KV outgoing /incomming OH power line	8.5	KM			0.00	INR Zero Only
10	Total impact of GST for the purpose of CTC	1.00	Nos			0.00	INR Zero Only
Total In Figures						0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only						