

Tender Inviting Authority: Staff Officer (Civil), Argada Area

Name of Work : "Repairing & periodic cleaning of ETP along with washing platform under Gidi-C Colliery for a period of Two years." (e-tender 40 of 25-26)

	Category of Services (To Be Selected by Department)	Category of Bidder(To Be Selected by Bidder)	To Be Entered by Department		
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth. 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m, disposed earth to be levelled and neatly dressed. 2.6.1 All kinds of soil	1531.25	M3	139.70	213915.63	INR Two Lakh Thirteen Thousand Nine Hundred & Fifteen and Paise Sixty Two Only
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	33.36	M3	205.80	6865.49	INR Six Thousand Eight Hundred & Sixty Five and Paise Forty Nine Only
3	Supplying and filling in plinth with Jamuna sand under floors including, watering, ramming consolidating and dressing complete.	3.13	M3	1438.10	4501.25	INR Four Thousand Five Hundred & One and Paise Twenty Five Only
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 4.1.5 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	3.54	M3	6773.95	23979.78	INR Twenty Three Thousand Nine Hundred & Seventy Nine and Paise Seventy Eight Only

5	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 5 in foundation and plinth in in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand)	26.53	M3	6770.05	179609.43	INR One Lakh Seventy Nine Thousand Six Hundred & Nine and Paise Forty Three Only
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	1.00	M3	7424.45	7424.45	INR Seven Thousand Four Hundred & Twenty Four and Paise Forty Five Only
7	12 mm cement plaster finished with a floating coat of neat cement of mix : 1:4 (1 cement: 4 fine sand)	128.95	M2	303.20	39097.64	INR Thirty Nine Thousand & Ninety Seven and Paise Sixty Four Only
8	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					475393.67	INR Four Lakh Seventy Five Thousand Three Hundred & Ninety Three and Paise Sixty Seven Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				