

Tender Inviting Authority: Staff Officer (Civil), Argada Area

Name of Work :	"Demarcation of Acquired Land Boundary of Religara Project under Religara, Argada Area." (e-tender 42 of 25-26)				
	Category of Services (To Be Selected by Department)	Category of Bidder(To Be Selected by Bidder)	To Be Entered by Department		
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT in Words
1	2	3	4	5	6	7
1	2.8.1 (Ref. CCL SOR 2025) Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.2.8.1 All kinds of soil.	72.00	M3	205.80	14817.60	INR Fourteen Thousand Eight Hundred & Seventeen and Paise Sixty Only
2	2.27 (Ref. CCL SOR 2025) Supplying and filling in plinth with Jamuna sand under floors, including watering, ramming, consolidating and dressing complete.	3.60	M3	1438.10	5177.16	INR Five Thousand One Hundred & Seventy Seven and Paise Sixteen Only
3	4.1.4 (Ref. CCL SOR 2025) Providing and laying in position cement concrete of specified garde 1:2:4 (1 cement : 2 coares sand : 4 graded stone aggregate 40 mm nominal size) excluding the cost of centering and shuttering -All work up to plinth level :	61.20	M3	7149.05	437521.86	INR Four Lakh Thirty Seven Thousand Five Hundred & Twenty One and Paise Eighty Six Only

4	16.15.1 (Ref. CCL SOR 2025) Supplying at site : 16.15.1 R.C.C. Standards post/ struts/rails/ pales of mix 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 12.5 mm nominal size) with wooden plugs or 6mm bar nibs wherever required as per direction of Engineer-incharge (cost of earth works in excavation, concrete works in foundation to be paid separately).	12.00	M3	25474.25	305691.00	INR Three Lakh Five Thousand Six Hundred & Ninety One Only
5	13.61.1 (Ref. CCL SOR 2025) Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :13.61.1 Two or more coats on new work	104.00	M2	112.30	11679.20	INR Eleven Thousand Six Hundred & Seventy Nine and Paise Twenty Only
6	13.71 (Ref. CCL SOR 2025) Lettering with black Japan paint of approved brand and manufacture.	23800.00	per letter per cm height	3.85	91630.00	INR Ninety One Thousand Six Hundred & Thirty Only
7	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					866516.82	INR Eight Lakh Sixty Six Thousand Five Hundred & Sixteen and Paise Eighty Two Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				