

Tender Inviting Authority: Staff Officer (Civil), Argada Area

Name of Work : "Repair and maintenance of Rest Shelter at Gidi-C under Gidi-C OCP of Argada Area." (e-tender 44 of 25-26)

	<b>Category of Services (To Be Selected by Department)</b>	<b>Category of Bidder( To Be Selected by Bidder)</b>	<b>To Be Entered by Department</b>		
<b>ITC Not Available</b>	<b>Works Contract</b>	<b>Bidder's Status (Mandatory)</b>	<b>Rate of GST (in %)</b>	<b>GST to be Paid By Bidder (in Rs.)</b>	<b>GST to be Paid By CIL/Subsidiary (in Rs.)</b>
<b>Name of the Bidder/ Bidding Firm / Company :</b>		<b>Select</b>	<b>18.00</b>	<b>0.00</b>	<b>0.00</b>

**PRICE SCHEDULE**

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT in Words
1	2	3	4	5	6	7
1	2.28.1 (Ref. CCL SOR 2025)Surface dressing of the ground including removing vegetation and in- equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m.All kinds of soil	239.00	M2	20.5	4899.50	INR Four Thousand Eight Hundred & Ninety Nine and Paise Fifty Only
2	16.68 (Ref CCL SOR 2025) Providing and laying 60 mm thick factory made cement concrete interlocking paver block of M - 30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge.	239.00	M2	670.05	160141.95	INR One Lakh Sixty Thousand One Hundred & Forty One and Paise Ninety Five Only
3	6.1.2(Ref. CCL SOR 2025)Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:Cement mortar 1:6(1 cement :6 coarse sand)	9.75	M3	6770.05	66007.99	INR Sixty Six Thousand & Seven and Paise Ninety Nine Only

4	11.41.2 (Ref. CCL SOR 2025)Providing and laying vitrified floor tiles in diferent sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20 mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete.Size of Tile 600x600 mm	33.14	M2	1385.2	45905.53	INR Forty Five Thousand Nine Hundred & Five and Paise Fifty Three Only
5	13.1.2 (Ref. CCL SOR 2025)12 mm cement plaster of mix:1:6(1 cement: 6 fine sand)	18.28	M2	230.6	4215.37	INR Four Thousand Two Hundred & Fifteen and Paise Thirty Seven Only
6	12.50 (Ref. CCL SOR 2025)Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-Charge) of total coated thickness 0.50 mm (base metal of minimum 0.45 mm thickness with total coating thickness of 0.05mm) with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	3.51	M2	698.10	2450.33	INR Two Thousand Four Hundred & Fifty and Paise Thirty Three Only
7	10.2 (Ref. CCL SOR 2025)Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	17.81	KG	114.90	2046.37	INR Two Thousand &Forty Six and Paise Thirty Seven Only

8	12.52.3 (Ref. CCL SOR 2025) Providing and fixing tiled false ceiling of specified materials of size 595x595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections ( galvanized @ 120 grams/ sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/making, opening for services like difusers, grills, light fittings, fixtures, smoke detectors etc. Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 x 37 x 25 x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanised butterfly level clips of size 85 x 30 x 0.8 mm spaced at 1200 mm center to center along main T, bottom exposed width of 24 mm of all T-sections shall be pre-painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-charge. 12.5 mm thick square edge PVC Laminated Gypsum Tile of size 595x595 mm, made of	60.80	M2	1773.2	107810.56	INR One Lakh Seven Thousand Eight Hundred & Ten and Paise Fifty Six Only
9	13.80 (Ref. CCL SOR 2025) Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	29.28	M2	114.95	3365.74	INR Three Thousand Three Hundred & Sixty Five and Paise Seventy Four Only
10	13.41.1 (Ref. CCL SOR 2025)Distempering with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gram/litre, of approved manufacturer and of required shade and colour all complete to achieve even shade and colour:New work (two or more coats) over and including water thinnable priming coat with cement primer having VOC content less than 50 gram/litre	99.89	M2	128.05	12790.91	INR Twelve Thousand Seven Hundred & Ninety and Paise Ninety One Only
11	15.13.1 (Ref. CCL SOR 2025)Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50 metres lead :Of area 3 sq. metres and below	1.00	EA	88.4	88.40	INR Eighty Eight and Paise Forty Only

12	4.1.6(Ref. CCL SOR 2025) Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 40 mm nominal size derived from natural sources)	0.25	M3	6480.4	1620.10	INR One Thousand Six Hundred & Twenty and Paise Ten Only
13	13.45.1 (Ref. CCL SOR 2025)Finishing walls with textured exterior paint of required shade:New work (Two or more coats applied @ 3.28 ltr/10 sqm) over and including priming coat of exterior primer applied @ 2.20kg/10 sqm	99.73	M2	202.45	20190.34	INR Twenty Thousand One Hundred & Ninety and Paise Thirty Four Only
14	<b>Total impact of GST for the purpose of CTC</b>	1.000	Nos	<b>0.00</b>	<b>0.00</b>	INR Zero Only
<b>Total in Figures</b>					<b>431533.08</b>	INR Four Lakh Thirty One Thousand Five Hundred & Thirty Three and Paise Eight Only
<b>Quoted Rate in Figures</b>			Select		<b>0.00</b>	INR Zero Only
<b>Quoted Rate in Words</b>						<b>INR Zero Only</b>