

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority: Staff officer (E&M), NK Area, CCL

Name of the Work / Contract No:	Repair, maintenance of 11kV GOAB switch, laying and handling of HT and LT cables, trench cutting, tree trimming, installation MCCB Switches, Making/ connection of earth pits with required accessories and electrification of switch room at Quarry No. 02 Substation (11kV/3.3kV/440V) under Purnadih OCP, NK Area	NIT No. GM (NK)/EnM/eNIT/2025-26/144; dated 28.03.2026.			
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be updated after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Repairing of 11kV, 800A GOAB by providing and fixing of fixed contact 11kV, 800A, 25kA.	24.00	Nos		0.00	INR Zero Only
2	Repairing of 11kV, 800A GOAB by providing and fixing of moving contact 11kV, 800A, 25kA.	10.00	Nos		0.00	INR Zero Only
3	Supply of Horn Gap Fuse unit 11kV grade Outdoor type	9.00	Nos		0.00	INR Zero Only
4	Providing and fixing of 11kV, 800A post insulator	20.00	Nos		0.00	INR Zero Only
5	Installation, testing and commissioning on item no. 1 to 3	1.00	job		0.00	INR Zero Only
6	Excavation for cable trenches in soft soil, depth upto 1.2 m including dressing of sides lift upto 1.5 m, including getting out the excavated soil, refilling with sand and or good soil after laying of cable/ pipe etc in layers of 20 cm, ramming, watering and disposal of surplus excavated soil as directed, within a lead of 50 metres.	40.00	cum		0.00	INR Zero Only

7	Cable handing/ lowering/ laying of one number PVC insulated and PVC sheathed / XLPE power cable of 11kV grade of following size in the existing masonry open duct as required. Up to 120 Sq. mm	80.00	Meter		0.00	INR Zero Only
8	Cable handing/ lowering/ laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1kV grade of following size in the existing masonry open duct as required. Up to 95 Sq. mm	80.00	Meter		0.00	INR Zero Only
9	Providing and fixing 630 A, 50 KA, TPMCCB rating and breaking capacity an dpole MCCB with thermomagnetic release and terminal spreaders in existing cubicle panel board including drilling holes in cubicle panel, making connections, etc. as required	4.00	Nos		0.00	INR Zero Only
10	Providing and fixing 25 mm X 5 mm copper strip on surface or in recess for connections etc. as required	25.00	Meter		0.00	INR Zero Only
11	Earthing with copper earth plate 600 mm X 600 mm X 3 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/ coke and salt as required	5.00	Nos		0.00	INR Zero Only
12	Tree trimming / branch cutting under Overhead lines.	2000.00	Sqm		0.00	INR Zero Only
13	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed steel conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc as required	8.00	Nos		0.00	INR Zero Only
14	Supplying and fixing metal box of 150 mm X 75 mm X 60 mm deep (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including providing and fixing 3 pin 5/6 amps socket outlet and 5/6 amps piano type switch, connection, painting etc. as required.	2.00	Nos		0.00	INR Zero Only
15	Supplying and fixing metal box of 180 mm X 100 mm X 60 mm deep (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including providing and fixing 6 pin 5/6 and 15/16 amps socket outlet and 15/16 amps piano type switch, connection, painting etc. as required	2.00	Nos		0.00	INR Zero Only
16	Supplying and fixing 3 pin, 5 amp ceiling rose on the existing junction box / wooden block including connection etc as required.	4.00	Nos		0.00	INR Zero Only
17	Supplying and fixing brass batten / angle holder including connection etc as required.	4.00	Nos		0.00	INR Zero Only
18	Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc as required	1.00	Nos		0.00	INR Zero Only
19	Providing and fixing following capacity TP&N disconnecter fuse switch unit inside the existing panel board with ISI marked HRC fuses including drilling holes in cubicle panel, making connections, etc as required. 32 Amp.	1.00	Nos		0.00	INR Zero Only

20	Supplying and fixing DP sheet steel enclosure on surface / recess along with 25/32 amps 240 volts "C" curve DP MCB complete with connections, testing and commissioning etc. as required.	1.00	Nos		0.00	INR Zero Only
21	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				