

**Item Rate BoQ**

Tender Inviting Authority:	Project Engineer (EnM), PEOCP, Hazaribagh Area					
Name of the Work / Contract No:	Maintenance/repairing/dismantling/lying of 8" and 10" dia 2 ranges pipe line installed at mine for dewatering purpose and pump-motor set shifting for monsoon preparation at Parej East Open Cast Project under Hazaribagh Area.					
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00

**PRICE SCHEDULE**

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Excavating trenches of required width for pipes,cable etc. exceeding 80 mm dia. but not exceeding 300mm dia including excavation for sockets and dressing of sides by mechanical / manual means ramming of bottoms for all depth including getting out the excavated soil and the returning the soil as required in layers no exceeding 20cm in depth including consolidating each deposited layer by ramming, watering etc. and disposing of surplus excavated soil as directed, within a lead of 50 m:	60	mtr			0.00	INR Zero Only
2	Dismantling of 200 mm dia. MS/GI pipe	96	mtr			0.00	INR Zero Only
3	Laying of 200 mm dia. MS/GI pipe	96	mtr			0.00	INR Zero Only
4	Dismantling of 250 mm dia. MS/GI pipe	75	mtr			0.00	INR Zero Only
5	Laying of 250 mm dia. MS/GI pipe	75	mtr			0.00	INR Zero Only
6	Making /Fabrication of 6" dia tapper/bend	6	nos.			0.00	INR Zero Only
7	Making /Fabrication of 8" dia tapper/bend	6	nos.			0.00	INR Zero Only
8	Making /Fabrication of 10" dia tapper/bend	6	nos.			0.00	INR Zero Only
9	Fabrication & fitting charge of 8"X 6" dia Nipple for suction & delivery	4	nos.			0.00	INR Zero Only
10	Dismantling, shifting and Installation of 1000 GPM/2000 GPM Pump set with base frame, suction pipeline, valves etc.	5	Nos.			0.00	INR Zero Only
11	Providing and fixing bolts including nuts and washers complete.	100	kg			0.00	INR Zero Only
12	Welding by gas or electric plant including transportation of plant at site etc. complete. (6" dia damaged pipe = 5000cm + 8" dia damaged pipe = 4000cm + 10" dia damaged pipe = 1000cm)	10000	cm			0.00	INR Zero Only
13	<b>Total impact of GST for the purpose of CTC</b>	1.00	No		0.00	0.00	INR Zero Only
<b>Total in Figures</b>						<b>0.00</b>	INR Zero Only
<b>Quoted Rate in Words</b>	<b>INR Zero Only</b>						