

**Item Rate BoQ**

Tender Inviting Authority: Project Engineer (E&M), Ashok OCP, Piparwar Area

<b>Name of the Work / Contract No:</b>	Laying of HDPE pipe 150mm dia and Layflat pipe length 490m from main pipe near coal transporting road to coal stock no- for spontaneous heating of coal and M.S.pipe 150mm dia length 790m (310+240+240)laying/extension/shifting from departmental patch to OB dump area for dewatering and dismantling 480m 150mm dia pipe from coal stock no- and laying 8" dia pipe line length 1290m from departmental patch to benti nala under Ashok O C P PPR Area.	<b>NIT No. :</b> PO(AK)/PE(EnM)/e-NIT/25-26/59
--	---	--

<b>Category of Services (To Be Selected by Department)</b>	<b>Category of Bidder (To Be Selected by Bidder)</b>	<b>To Be Entered by Department</b>				
<b>ITC Available</b>	<b>Works Contract</b>	<b>Bidder's Status (Mandatory)</b>		<b>Total GST(in Rs.)</b>	<b>GST to be Paid By Bidder (in Rs.)</b>	<b>GST to be Paid By CIL/Subsidiary (in Rs.)</b>
<b>Name of the Bidder/ Bidding Firm / Company :</b>		<b>Select</b>	<b>18</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>

**PRICE SCHEDULE**  
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate (Without taxes) in Rs. P	BASIC RATE (Without taxes) in Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	Laying of HDPE pipe 150mm dia 490m from main pipe line to coal stock no- five unskilled labour and one semi skilled person in group.(541x5+674=3379x1.15=3885.85)	5	Group	3885.85		0.00	INR Zero Only
2	Dismantling of HDPE pipe 150mm dia 490m from main pipe line to coal stock no- five unskilled labour and one semi skilled person in group.(541x5+674=3379x1.15=3885.85)	4	Group	3886.85		0.00	INR Zero Only
3	Carriage of 6" dia pipe from substation store to site for 2km distance	790	Mtr	4.26		0.00	INR Zero Only
4	Joint making/ flange fixing by centering and welding and U/L type band and short peace etc for 6" dia pipe	77.64	Mtr	360.00		0.00	INR Zero Only
5	Laying in position, cast/spun iron S&S or flanged pipe for 6" dia pipe	160.9	Quintel	224.60		0.00	INR Zero Only
6	Excavating trenches of required width for pipes, cables, etc including excavation for sockets, addressingof sides,bymechnical /manual means For 6" dia pipe	83	Mtr	250.40		0.00	INR Zero Only
7	Dismantling of 150mm dia pipe by gas cutting length 480m	44.65	Mtr	360.00		0.00	INR Zero Only
8	Providing and fixing bolts including nuts and washers complete.	45	Kg	109.60		0.00	INR Zero Only
9	Laying in position, cast/spun iron S&S or flanged pipe for 8" dia pipe	327.66	Quintel	224.60		0.00	INR Zero Only
10	Excavating trenches of required width for pipes, cables, etc including excavation for sockets, addressingof sides,bymechnical /manual means For 8" dia pipe	163	Mtr	250.40		0.00	INR Zero Only
11	Providing and fixing bolts including nuts and washers complete.	72	Kg	109.60		0.00	INR Zero Only
12	Joint making/ flange fixing by centering and welding and U/L type band and short peace etc for 6" dia pipe	174.12	Mtr	360.00		0.00	INR Zero Only
13	<b>Total impact of GST for the purpose of CTC</b>	1.000	Nos		<b>0.00</b>	<b>0.00</b>	INR Zero Only
<b>Total in Figures</b>						<b>0.00</b>	INR Zero Only
<b>Quoted Rate in Words</b>							<b>INR Zero Only</b>