

Tender Inviting Authority: Staff officer (E&M), NK Area, CCL					
Name of the Work / Contract No:	Maintenance of 3.3 kV Overhead line, colony feeder and LT Overhead line for monsoon preparation under Rohini Project, NK Area	NIT No. GM (NK)/EnM/eNIT/2025-26/145; dated 30.03.2026.			
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be updated after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Erection of steel tubular or rail pole strut in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc as required. Above 10.00 meters and up to 12.00 meters	11.00	Nos		0.00	INR Zero Only
2	Erection of ACSR conductor of 7/3.35 mm to 7/4.00 diameter and above including binding etc. as required	513.00	Kg		0.00	INR Zero Only
3	Supplying and erection of stay set complete (galvanised) with 19/20 mm dia X 1.8 metres long stay rod, anchor plate of size 45 cm X 45 cm X 7.5 mm, thimble, stay clamps, bow tightener, 7/ 4.00 mm dia G.I. stay wire and strain insulator etc in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc. as required	7.00	Set		0.00	INR Zero Only
4	Erection of double pole 3 wire cross arm for 11KV over head lines as required	12.00	Set		0.00	INR Zero Only
5	Erection of disc/ pin insulator for 11 KV over head lines as required	15.00	Set		0.00	INR Zero Only

6	Supplying of two lengths of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) double pole cross arm for three wire 11KV over head line conductors complete with through bolts and nuts for clamping to the poles, 50 mm X 6 mm M.S. flats welded on one side to the channel iron and with bolts and nuts on the other side for tying the cross arms together, including drilling holes for insulator pins/ fittings, bolts, nuts and washers etc (as per drawing) and painting with primer and finish paint as required	6.00	Set		0.00	INR Zero Only
7	Erection of pole top/ straight two wire/ V shape two wire, angle iron/ channel iron, cross arm on steel tubular/ rail/ PCC pole for 11/22/33 KV as required	5.00	Set		0.00	INR Zero Only
8	Supply of 6 SWG G.I. wire	150.00	Kg		0.00	INR Zero Only
9	Erection of G.I. Wire No. 8 SWG including binding etc. as required	50.00	Kg		0.00	INR Zero Only
10	Supplying and erection of disc insulator for 11 KV over head lines with galvanised insulator fittings, ball and socket type and complete with galvanised strain clamps, bolts, nuts, washers etc. as required	18.00	Set		0.00	INR Zero Only
11	Dismantling of pole/ street light standard/ strut embedded in cement concrete foundation etc. as required	7.00	Nos		0.00	INR Zero Only
12	Dismantling of over head lines comprising of copper/ aluminium over head conductor, G.I. wire, cross arms, insulators etc. as required	650.00	Kg		0.00	INR Zero Only
13	Supplying and erection of 11 KV pin insulator complete with large steel head G.I. pin, nuts, washers etc. as required	30.00	Set		0.00	INR Zero Only
14	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) V shape cross arm for two 11 KV over head line conductors complete with 50 mm X 6mm M.S. flat iron clamps, bolts and nuts including drilling holes for insulator pins, bolts, nuts and washers etc (as per drawing) and painting with primer and finish paint as required	5.00	Set		0.00	INR Zero Only
15	Supplying of channel iron 75 mm X 40 mm X 6 mm (7.14 kg per metre) pole top bracket/ cross arm for single 11 KV over head line conductor complete with 50 mm X 6mm flat iron clamp, bolts, nuts and washers including drilling holes for insulator pins, bolts and nuts etc and painting with primer and finish paint as required	5.00	Set		0.00	INR Zero Only
16	Erection of cradle guard as required.	100.00	Nos		0.00	INR Zero Only
17	Supplying and erection of a set of cross bracing frame work for 11 KV over head line double pole structure having four members fabricated out of 50mm x 50mm x 6mm angle iron to form a rectangle of minimum size 1400 mm width x 2500 mm height, complete with 50 mm x 6mm MS Flats iron clamps, bolts and nuts including drilling holes for insulator pins, bolts, nuts etc. and painting with primer and finish paint ,as required.	5.00	Set		0.00	INR Zero Only

18	Tree trimming / branch cutting under Overhead lines.	1500.00	Sqm		0.00	INR Zero Only
19	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only					