

Item Rate BoQ

Tender Inviting Authority: Project Engineer(E&M), Bhurkunda Colliery, Barka-Sayal Area, CCL.

Name of the Work / Contract No:	Supply and fixing of TPN (100 Amps, 200 Amps, 400 Amps and 63 Amps) with MCCB (400A, 630A and 250A) for different location under Bhurkunda Colliery.	NIT No. : PE(EnM)/BHK/e Tender/25-26/56	Dated:30/03/2026
---------------------------------	--	---	------------------

Category of Services (To Be Selected by Department)		Category of Bidder (To Be Selected)			
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00

PRICE SCHEDULE
 (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	12	6	7	8
1	Providing and fixing following capacity TP&N disconnector fuse switch unit inside the existing panel board with ISI marked HRC fuses including drilling holes in cubicle panel, making connections, etc. as required. 100A TP&N	4.00	Nos.	INR		0.00	INR Zero Only
2	Providing and fixing following capacity TP&N disconnector fuse switch unit inside the existing panel board with ISI marked HRC fuses including drilling holes in cubicle panel, making connections, etc. as required. 200A TP&N	5.00	No.	INR		0.00	INR Zero Only
3	Providing and fixing following capacity TP&N disconnector fuse switch unit inside the existing panel board with ISI marked HRC fuses including drilling holes in cubicle panel, making connections, etc. as required. 400A TP&N	3.00	No.	INR		0.00	INR Zero Only
4	Providing and fixing following capacity TP&N disconnector fuse switch unit inside the existing panel board with ISI marked HRC fuses including drilling holes in cubicle panel, making connections, etc. as required. 63A TP&N	6.00	No.	INR		0.00	INR Zero Only
5	Providing and fixing following rating and breaking capacity and pole MCCB with thermomagnetic release and terminal spreaders in existing cubicle panel board including drilling holes in cubicle panel, making connections, etc. as required. 400 A,50KA,FPMCCB	3.00	No.	INR		0.00	INR Zero Only
6	Providing and fixing following rating and breaking capacity and pole MCCB with thermomagnetic release and terminal spreaders in existing cubicle panel board including drilling holes in cubicle panel, making connections, etc. as required. 630 A,50KA,FPMCCB	3.00	No.	INR		0.00	INR Zero Only
7	Providing and fixing following rating and breaking capacity and pole MCCB with thermomagnetic release and terminal spreaders in existing cubicle panel board including drilling holes in cubicle panel, making connections, etc. as required. 250 A,36KA,FPMCCB	3.00	No.	INR		0.00	INR Zero Only
8	Total impact of GST for the purpose of CTC	1.000	Nos	INR	0.00	0.00	INR Zero Only
Total In Figures						0.00	INR Zero Only
Quoted Rate in Words						INR Zero Only	