

Tender Inviting Authority: Staff officer(E&M), Dhori Area.							
Name of the Work / Contract No:	Repair and Maintenance of 11KV OH line from Dhori Sub-station to SDOCM substation including damage pole replacement tree trimming and other accessories under SDOCM project of Dhori Area.						
	Category of Services (To Be Selected by Department)		Category of Bidder (To Be)	To Be Entered by Department			
I TC Available	Works Contract		Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :			Select	18	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
0.1	Erection of ACSR conductor of 7/3.35 mm to 7/4.0 diameter and above including binding etc as required 1.6km x 3wire = 4.8 km x 394 kg /km = 1891.20 kg	1891.2	Kg			0.00	INR Zero Only
0.2	Supplying of channel iron 50 mm x 8 mm M.S.flat iron pole top bracket cross arm for single 11 KV OH line conductor complete with fixing clamps bolts and nuts including drilling holes for insulators pins bolt and nut etc and painting with primer and finish paint as required	2	Each			0.00	INR Zero Only
0.3	Supplying of Channel iron 75 mm x 40 mm x 6 mm (7.14 kg per mtr). bracket cross arm for two 11 KV OH line conductor complete with 50 mm x 50 mm x 6 mm angle iron welded to the channel iron and complete with 50 mm x 6 mm M.S Flat iron clamps, bolts, nuts and including drilling holes for insulators pins bolt, nuts and washers etc (as per drawing) and painting with primer and finish paint as required	2	Each			0.00	INR Zero Only
0.4	Supply and erection of 11 KV Pin insulator complete with large steel head GI in nuts and washers etc as required.	36	set			0.00	INR Zero Only
0.5	Supply and erection of 11 kv disc insulator for 11KV over head lines with galvanised insulator fittings ball and socket type and complete with strain clamps, bolt nut washers etc.as required.	12	Set			0.00	INR Zero Only
0.6	Erection of pole top and straight two wire angle iron channel cross arm on steel tublor/Rail pole for 11KV as required	4	Set			0.00	INR Zero Only
0.7	Supply and erection of Galvanised stay set for 11 KV OH line complete with 19/20 mm dia x 1.8 mtr long stay rod, anchor plate of size 45 cm x 45 cm x 7.5 mm thick, thimble, stay clamps ,turn buckle (20 mm x 600 mm) 7/4.00 mm dia GI stay wire and 11 KV strain insulator etc in cement concrete 1:3:6 (1 cement :3 coarse sand :6 graded stone aggregate 40 mm nominal size) foundation including excavation and refilling etc as required.	2	Set			0.00	INR Zero Only
0.8	Dismantling of over head lines comprising of aluminium over head conductor, G.I. wire, cross arms, insulators etc as required. Conductor	2177.24	Kg			0.00	INR Zero Only
0.9	Providing of 11 kv, 400 A Male contact Blade suitable for GOS	6	Each			0.00	INR Zero Only
1	Providing of 11 kv, 400 A Female contact Blade suitable for GOS	6	Each			0.00	INR Zero Only
1.1	Repairing of 400 Amps Gang Operating Switch.	2	set			0.00	INR Zero Only
1.2	Supply of 8 SWG GI wire for earth continuity (800m x 0.131 kg/mtr= 104.80 kg)	104.80	Kg			0.00	INR Zero Only
1.3	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30 cm measured at a height of 1m above ground level and removal of rubbish upto a distance of 50 m outside the periphery of the area cleared for maintenance.	9600	Sqm			0.00	INR Zero Only
1.4	Connection of 11 KV OH line jumper as required	36	Nos			0.00	INR Zero Only
1.5	Patrolling, checking, testing of 11 KV OH line for routine maintenance and breakdown as and when required for a route length of 5 KM	25	Times			0.00	INR Zero Only
1.6	Erection of 8 SWG GI Wire including binding etc as required.	104.8	Kg			0.00	INR Zero Only
2.9	Total impact of GST for the purpose of CTC	1.000	Nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only						