

Validate

Print

Help

Percentage BoQ

Tender Inviting Authority: S.O(Civil), Rajrappa Area

Name of Work :-Providing RCC guard wall and drain near RFID entry and exit Point near check post No.3 under Rajrappa Area

	Category of Services (To Be Selected by Department)	Category of Bidder(To Be Selected by Bidder)	To Be Entered by Department		
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means In foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), Including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.All kinds of soil.	30.00	Cum	205.80	6174.00	INR Six Thousand One Hundred & Seventy Four Only
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:4:8 (1 Cement: 4 coarse sand (zone-III) derived from natural sources: 8 graded stone aggregate 40 mm nominal size derived from natural sources)	5.00	Cum	6072.40	30362.00	INR Thirty Thousand Three Hundred & Sixty Two Only
3	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level:1:2:4 (1 cement: 2 coarse sand (zone-III) derived from natural sources: 4 graded stone aggregate 20 mm nominal size derived from natural sources)	24.19	Cum	7860.35	190118.29	INR One Lakh Ninety Thousand One Hundred & Eighteen and Paise Twenty Nine Only
4	12 mm cement plaster of mix:1:6(1 cement: 6 fine sand)	101.00	Sqm	230.60	23290.60	INR Twenty Three Thousand Two Hundred & Ninety and Paise Sixty Only
5	Centering and shuttering including strutting, propping etc. and removal of form forFoundations, footings, bases of columns, etc. for mass concrete	15.00	Sqm	277.90	4168.50	INR Four Thousand One Hundred & Sixty Eight and Paise Fifty Only
6	Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc. Walls (any thickness) including attached pilasters, buttersesses, plinth and string courses etc.	125.00	Sqm	562.75	70343.75	INR Seventy Thousand Three Hundred & Forty Three and Paise Seventy Five Only
7	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	2418.75	Kg	105.60	255420.00	INR Two Lakh Fifty Five Thousand Four Hundred & Twenty Only
8	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/litre, of approved brand and manufacture, Including applying additional coats wherever required, to achieve even shade and colour. Two coats	62.50	Sqm	103.95	6496.88	INR Six Thousand Four Hundred & Ninety Six and Paise Eighty Eight Only
9	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-In-charge. Ordinary rock.	7.20	Cum	312.25	2248.20	INR Two Thousand Two Hundred & Forty Eight and Paise Twenty Only

10	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:2:4 (1 cement: 2 coarse sand (zone-III) derived from natural sources: 4 graded stone aggregate 20 mm nominal size derived	6.60	Cum	7424.45	49001.37	INR Forty Nine Thousand & One and Paise Thirty Seven Only
11	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50 mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks Into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-Charge.80 mm thick C.C. paver block of M-35 grade with approved colour design and pattern.	24.00	Sqm	837.95	20110.80	INR Twenty Thousand One Hundred & Ten and Paise Eighty Only
12	Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc. for mass concrete	4.00	Sqm	277.90	1111.60	INR One Thousand One Hundred & Eleven and Paise Sixty Only
13	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm In depth, 1.5 m in width as well as 10 sqm on plan) Including getting out and disposal of excavated earth lead upto 50 m and for all lift, as directed by Engineer-in charge.All kinds of soil	165.00	Cum	139.70	23050.50	INR Twenty Three Thousand & Fifty and Paise Fifty Only
14	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	6.25	Cum	1438.10	8988.13	INR Eight Thousand Nine Hundred & Eighty Eight and Paise Twelve Only
15	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:3:6 (1 Cement: 3 coarse sand (zone-III) derived from natural sources: 6 graded stone aggregate 40 mm nominal size derived from natural sources)	7.25	Cum	6480.40	46982.90	INR Forty Six Thousand Nine Hundred & Eighty Two and Paise Ninety Only
16	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 In foundation and plinth In:Cement mortar 1:6(1 cement:6 coarse sand)	25.00	Cum	6770.05	169251.25	INR One Lakh Sixty Nine Thousand Two Hundred & Fifty One and Paise Twenty Five Only
17	12 mm cement plaster finished with a floating coat of neat cement of mix:1:4(1 cement: 4 fine sand)	162.50	Sqm	303.20	49270.00	INR Forty Nine Thousand Two Hundred & Seventy Only
18	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), Including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.All kinds of soil.	40.50	Cum	205.80	8334.90	INR Eight Thousand Three Hundred & Thirty Four and Paise Ninety Only
19	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering All work up to plinth level:1:4:8 (1 Cement: 4 coarse sand (zone-III) derived from natural sources: 8 graded stone aggregate 40 mm nominal size derived from natural sources)	2.70	Cum	6072.40	16395.48	INR Sixteen Thousand Three Hundred & Ninety Five and Paise Forty Eight Only
20	Providing and laying Reinforced Cement Concrete Pipe NP4/prestrssed concrete pipe on first class bedding in single row. (Providing and Laying Reinforced cement concrete pipe NP4/prestrssed concrete pipe for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets) 1000	15.00	m	7349.00	110235.00	INR One Lakh Ten Thousand Two Hundred & Thirty Five Only
21	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:4:8 (1 Cement: 4 coarse sand (zone-III) derived from natural sources: 8 graded stone aggregate 40 mm nominal size derived from natural sources)	4.05	Cum	6072.40	24593.22	INR Twenty Four Thousand Five Hundred & Ninety Three and Paise Twenty Two Only
22	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:2:4 (1 cement: 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	5.40	Cum	7424.45	40092.03	INR Forty Thousand & Ninety Two and Paise Three Only
23	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:Cement mortar 1:6(1 cement : 6 coarse sand)	3.37	Cum	6770.05	22787.99	INR Twenty Two Thousand Seven Hundred & Eighty Seven and Paise Ninety Nine Only
24	12 mm cement plaster finished with a floating coat of neat cement of mix:1:4(1 cement: 4 fine sand)	9.27	Sqm	303.20	2810.97	INR Two Thousand Eight Hundred & Ten and Paise Ninety Seven Only
25	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					1181638.34	INR Eleven Lakh Eighty One Thousand Six Hundred & Thirty Eight and Paise Thirty Four Only

Quoted Rate in Figures		Select		0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only				