

Tender Inviting Authority: S.O(Civil), Rajrappa Area

Name of Work :-Cleaning of drains, hume pipe and providing hume pipes at required location of sec 1 and sec 2 under Rajrappa project.

	Category of Services (To Be Selected by Department)	Category of Bidder(To Be Selected by Bidder)	To Be Entered by Department		
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00

PRICE SCHEDULE
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT in Words
1	2	3	4	5	6	7
1	Excavation in Soil using Hydraulic Excavator and Tipper with disposal upto 1000 metres. (Excavation for roadwork in soil with	11592.90	cum	66.50	770927.85	INR Seven Lakh Seventy Thousand Nine Hundred & Twenty Seven and Paise Eighty Five Only
2	Providing and laying Non Pressure NP-4 class (Heavy duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement .1000 mm dia RCC pipes. (Laying by manual/ mechanical means)	125.00	m	7576.55	947068.75	INR Nine Lakh Forty Seven Thousand & Sixty Eight and Paise Seventy Five Only
3	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	9.38	Cum	1438.10	13489.38	INR Thirteen Thousand Four Hundred & Eighty Nine and Paise Thirty Eight Only
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size).	18.75	Cum	6480.40	121507.50	INR One Lakh Twenty One Thousand Five Hundred & Seven and Paise Fifty Only
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	6.25	cum	7424.45	46402.81	INR Forty Six Thousand Four Hundred & Two and Paise Eighty One Only
6	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared.	2000.00	sqm	10.55	21100.00	INR Twenty One Thousand One Hundred Only
7	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					1920496.29	INR Nineteen Lakh Twenty Thousand Four Hundred & Ninety Six and Paise Twenty Nine Only
Quoted Rate in Figures			Select		0.00	INR Zero Only

Quoted Rate in Words

INR Zero Only