

Tender Inviting Authority: S.O(Civil), Rajrapa Area

Name of Work :-Cleaning of drain Providing roofing sheet at damaged portions and trimming under Rajrapa Washery Project.

	<b>Category of Services (To Be Selected by Department)</b>	<b>Category of Bidder( To Be Selected by Bidder)</b>	<b>To Be Entered by Department</b>		
<b>ITC Not Available</b>	<b>Works Contract</b>	<b>Bidder's Status (Mandatory)</b>	<b>Rate of GST (in %)</b>	<b>GST to be Paid By Bidder (in Rs.)</b>	<b>GST to be Paid By CIL/Subsidiary (in Rs.)</b>
<b>Name of the Bidder/ Bidding Firm / Company :</b>		<b>Select</b>	<b>18.00</b>	<b>0.00</b>	<b>0.00</b>

**PRICE SCHEDULE**

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT in Words
1	2	3	4	5	6	7
1	Providing corrugated G.S. sheet roofing including Providing corrugated vertical/curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.0.63 mm thick with zinc coating not less than 275gm/m²	45.00	Sqm	883.75	39768.75	INR Thirty Nine Thousand Seven Hundred & Sixty Eight and Paise Seventy Five Only
2	Extra for providing and fixing wind ties of 40x 6mm flat iron section.	25.00	m	175.35	4383.75	INR Four Thousand Three Hundred & Eighty Three and Paise Seventy Five Only
3	Pruning, trimming, shaping of trees/shrubs (ht15ftctandabove) i/removal of cutmaterialsupto50mt.Lead, asperdirectionof officer in charge. T&P shall be arranged by the contractor.	750.00	each	86.15	64612.50	INR Sixty Four Thousand Six Hundred & Twelve and Paise Fifty Only
4	Excavation in Soil using Hydraulic Excavator and Tipper with disposal upto 1000 metres. (Excavation for roadwork in soil with hydraulic excavator including cutting and loading in tipper, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transporting to the embankment location within all lifts and lead upto 1000m nominal size).	1023.48	Cum	66.50	68061.42	INR Sixty Eight Thousand & Sixty One and Paise Forty Two Only
5	Clearing jungle including uprooting of rankvegetation, grass, brushwood, treesandsaplingsof girthupto 30cmmeasuredata height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared.	1000.00	Sqm	10.55	10550.00	INR Ten Thousand Five Hundred & Fifty Only
6	<b>Total impact of GST for the purpose of CTC</b>	1.000	Nos	0.00	0.00	INR Zero Only
<b>Total in Figures</b>					<b>187376.42</b>	INR One Lakh Eighty Seven Thousand Three Hundred & Seventy Six and Paise Forty Two Only
<b>Quoted Rate in Figures</b>			<b>Select</b>		<b>0.00</b>	INR Zero Only

Quoted Rate in Words

INR Zero Only