

Tender Inviting Authority: Staff Officer(Civil), Kuju Area

Name of Work : Providing and fixing of 16 nos. 1000 mm dia NP-4 Hume pipe at different locations in mines and Cleaning of settling tank of volume 270.00 cum and Cleaning & repairing of existing garland drain of length 1645.00 m and cu

	Category of Services (To Be Selected by Department)	Category of Bidder(To Be Selected by Bidder)	To Be Entered by Department		
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00

PRICE SCHEDULE
 (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
0	Item Description/ Heading					
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	4612.80	Cum	205.80	949314.24	INR Nine Lakh Forty Nine Thousand Three Hundred & Fourteen and Paise Twenty Four Only
2	Providing and laying Non Pressure NP-4 class (Heavy duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete. 1000 mm dia RCC pipes. (Laying by manual/ mechanical means).	40.00	Mtr	7576.55	303062.00	INR Three Lakh Three Thousand & Sixty Two Only
3	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	265.60	Sqm	118.65	31513.44	INR Thirty One Thousand Five Hundred & Thirteen and Paise Forty Four Only
4	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					1283889.68	INR Twelve Lakh Eighty Three Thousand Eight Hundred & Eighty Nine and Paise Sixty Eight Only
Quoted Rate in Figures			Select		0.00	INR Zero Only

Quoted Rate in Words

INR Zero Only