

Tender Inviting Authority: Staff Officer(Civil), Kuju Area

Name of Work : Providing and fixing of 24 nos. Hume pipe 1000 mm dia (NP-4) at different locations in mines and Cleaning & repairing of existing garland drains of length 2150 m and cutting of new garland drains of length 680 m, at differ

	<b>Category of Services (To Be Selected by Department)</b>	<b>Category of Bidder( To Be Selected by Bidder)</b>	<b>To Be Entered by Department</b>		
<b>ITC Available</b>	<b>Works Contract</b>	<b>Bidder's Status (Mandatory)</b>	<b>Rate of GST (in %)</b>	<b>GST to be Paid By Bidder (in Rs.)</b>	<b>GST to be Paid By CIL/Subsidiary (in Rs.)</b>
<b>Name of the Bidder/ Bidding Firm / Company :</b>		<b>Select</b>	<b>18.00</b>	<b>0.00</b>	<b>0.00</b>

**PRICE SCHEDULE**  
 (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
0	<b>Item Description/ Heading</b>					
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil	3847.20	Cum	205.80	<b>791753.76</b>	INR Seven Lakh Ninety One Thousand Seven Hundred & Fifty Three and Paise Seventy Six Only
2	Providing and laying Non Pressure NP-4 class (Heavy duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete. 1000 mm dia RCC pipes. (Laying by manual/ mechanical means).	60.00	Mtr	7576.55	<b>454593.00</b>	INR Four Lakh Fifty Four Thousand Five Hundred & Ninety Three Only
3	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	408.90	Sqm	118.65	<b>48515.99</b>	INR Forty Eight Thousand Five Hundred & Fifteen and Paise Ninety Nine Only
4	<b>Total impact of GST for the purpose of CTC</b>	1.000	Nos	<b>0.00</b>	<b>0.00</b>	INR Zero Only
<b>Total in Figures</b>					<b>1294862.75</b>	INR Twelve Lakh Ninety Four Thousand Eight Hundred & Sixty Two and Paise Seventy Five Only
<b>Quoted Rate in Figures</b>			<b>Select</b>		<b>0.00</b>	INR Zero Only

Quoted Rate in Words

INR Zero Only