

Validate

Print

Help

Percentage BoQ

Tender Inviting Authority: Staff Officer(Civil), Magadh-Sanghmitra Area

Name of Work : Providing and Laying of hume pipes under Magadh OCP of Magadh-Sanghmitra Area. (e NIT No. 77 of 2025-26)

	Category of Services (To Be Selected by Department)	Category of Bidder(To Be Selected by Bidder)	To Be Entered by Department		
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Excavation in Soil using Hydraulic Excavator and Tipppers with disposal upto 1000 metres. (Excavation for roadwork in soil with hydraulic excavator including cutting and loading in tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transporting to the embankment location within all lifts and lead upto 1000m)	8150.00	Cum	66.50	541975.00	INR Five Lakh Forty One Thousand Nine Hundred & Seventy Five Only
2	Providing and laying Non Pressure NP-4 class (Heavy duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete. 600 mm dia RCC pipes.	165.00	metre	3238.30	534319.50	INR Five Lakh Thirty Four Thousand Three Hundred & Nineteen and Paise Fifty Only
3	Providing and laying Reinforced Cement Concrete Pipe NP4/prestrssed concrete pipe on first class bedding in single row . (Providing and Laying Reinforced cement concrete pipe NP4/prestrssed concrete pipe for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets): 1000 mm dia	347.50	Mtr	7349.00	2553777.50	INR Twenty Five Lakh Fifty Three Thousand Seven Hundred & Seventy Seven and Paise Fifty Only
4	Providing and laying Reinforced Cement Concrete Pipe NP4/prestrssed concrete pipe on first class bedding in single row . (Providing and Laying Reinforced cement concrete pipe NP4/prestrssed concrete pipe for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets) : 1200 mm dia	140.00	Mtr	9169.00	1283660.00	INR Twelve Lakh Eighty Three Thousand Six Hundred & Sixty Only
5	Embankment Construction with Material Obtained from Borrow Pits (Construction of embankment with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement of table 300-2)	4655.00	Cum	133.70	622373.50	INR Six Lakh Twenty Two Thousand Three Hundred & Seventy Three and Paise Fifty Only
6	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					5536105.50	INR Fifty Five Lakh Thirty Six Thousand One Hundred & Five and Paise Fifty Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only					