

Validate		Print		Help		Percentage BoQ			
Tender Inviting Authority: Project Engineer (civil),CCL, Kathara									
Name of Work:Cleaning of Garland drain, pucca drain near Pit Office, base workshop and unit store, Kutcha drain cutting along the haul road at Kathara mines under Kathara Colliery, Kathara Area									
		Category of Services (To Be Selected by Department)		Category of Bidder(To Be Selected by Bidder)		To Be Entered by Department			
ITC Available		Works Contract		Bidder's Status (Mandatory)		Rate of GST (in %)		GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :				Select		18.00		0.00	0.00
PRICE SCHEDULE									
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)									
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #			
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words			
1	2	3	4	5	6	7			
1	Item Description/ Heading								
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	5400.00	cum	205.80	1111320.00	INR Eleven Lakh Eleven Thousand Three Hundred & Twenty Only			
3	Carriage of materials By Mechanical Transport including loading,unloading and stacking Earth Lead - 5 km	520.00	cum	224.10	116532.00	INR One Lakh Sixteen Thousand Five Hundred & Thirty Two Only			
4	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared.	4000.00	sqm	10.55	42200.00	INR Forty Two Thousand Two Hundred Only			
5	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only			
Total in Figures					1270052.00	INR Twelve Lakh Seventy Thousand & Fifty Two Only			
Quoted Rate in Figures		Select			0.00	INR Zero Only			
Quoted Rate in Words		INR Zero Only							

