

Validate

Print

Help

Percentage BoQ

Tender Inviting Authority: Staff Officer (Civil), Barka-Sayal Area

Name of Work: Cleaning of existing garland drains, cleaning of sedimentation pond, cutting new garland drains, provision of concrete pipe culverts and pump foundation under monsoon preparation works of Urimari Project, Barka-Sayal Area.

	Category of Services (To Be Selected by Department)	Category of Bidder(To Be Selected by Bidder)	To Be Entered by Department		
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT in Words
1	2	3.00	4	5	6	7
1	Item Description/ Heading					
1.01	Earth work in excavation by mechanical means (Hydraulic Excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.All kinds of soil.	4785.000	Cum	202.03	966713.55	INR Nine Lakh Sixty Six Thousand Seven Hundred & Thirteen and Paise Fifty Five Only
1.02	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and for all lift, as directed by Engineer-in-charge.	1990.400	Cum	139.70	278058.88	INR Two Lakh Seventy Eight Thousand & Fifty Eight and Paise Eighty Eight Only
1.03	Providing and laying Reinforced Cement Concrete Pipe NP4/prestrssed concrete pipe on first class bedding in single row . (Providing and Laying Reinforced cement concrete pipe NP4/prestrssed concrete pipe for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets)1200 mm dia	50.000	Meter	9169.00	458450.00	INR Four Lakh Fifty Eight Thousand Four Hundred & Fifty Only

1.04	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources)	20.000	Cum	6773.95	135479.00	INR One Lakh Thirty Five Thousand Four Hundred & Seventy Nine Only
1.05	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :1:1.5:3(1 cement: 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	22.680	cum	8343.450	189229.45	INR One Lakh Eighty Nine Thousand Two Hundred & Twenty Nine and Paise Forty Five Only
1.06	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.Thermo-Mechanically Treated bars of grade Fe-500D or more.	2041.200	kg	105.600	215550.72	INR Two Lakh Fifteen Thousand Five Hundred & Fifty and Paise Seventy Two Only
1.07	Centering and shuttering including strutting, propping etc. and removal of form forFoundations, footings, bases of columns, etc. for mass concrete	23.400	sqm	277.900	6502.86	INR Six Thousand Five Hundred & Two and Paise Eighty Six Only
1.08	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared.	6000.000	Sqm	10.55	63300.00	INR Sixty Three Thousand Three Hundred Only
1.09	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. All kinds of Soil	2000.000	Sqm	20.50	41000.00	INR Forty One Thousand Only
1.10	Total impact of GST for the purpose of CTC	1.00	Nos	0.00	0.00	INR Zero Only
Total in Figures					2354284.46	INR Twenty Three Lakh Fifty Four Thousand Two Hundred & Eighty Four and Paise Forty Six Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only					