

Tender Inviting Authority: Staff Officer(Civil), Rajhara Area.						
Name of Work: Making shed and platform for pump, transformer and switches at various locations in mine at Rajhara OCP under Rajhara Area						
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00	
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Earthwork in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm in plan), including dressing of sides and ramming of bottoms, for all lifts, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. 2.8.1 All kinds of soil.	15.92	cum	205.80	3276.34	INR Three Thousand Two Hundred & Seventy Six and Paise Thirty Four Only
2	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete. 1 cum 1844.00	2.62	cum	1438.10	3767.82	INR Three Thousand Seven Hundred & Sixty Seven and Paise Eighty Two Only
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement: 4 coarse sand (zone-III) derived from natural sources: 8 graded stone aggregate 40mm nominal size derived from natural sources)	2.22	cum	6072.40	13480.73	INR Thirteen Thousand Four Hundred & Eighty and Paise Seventy Three Only
4	Brickwork with common burnt clay F.P.S. (non-modular) bricks of class designation 7.5 in foundation and plinth in: 6.1.2 Cement mortar 1:6 (1 cement : 6 coarse sand) 1 cum 5322.15	17.50	cum	6770.05	118475.88	INR One Lakh Eighteen Thousand Four Hundred & Seventy Five and Paise Eighty Eight Only
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement: 2 coarse sand (zone-III) derived from natural sources: 4 graded stone aggregate 20mm nominal size derived from natural sources)	9.40	cum	7424.45	69789.83	INR Sixty Nine Thousand Seven Hundred & Eighty Nine and Paise Eighty Three Only

6	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. 1 kg 77.95	693.04	Kg	107.00	74155.28	INR Seventy Four Thousand One Hundred & Fifty Five and Paise Twenty Eight Only
7	Providing and fixing pre-coated galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-Charge) of total coated thickness 0.50 mm (base metal of minimum 0.45 mm thickness with total coating thickness of 0.05 mm) with zinc coating 120 grams per sq m as per IS: 277, in 240 MP steel grade, 5-7 micron epoxy primer on both side of the sheet and polyester	54.08	sqm	698.10	37753.25	INR Thirty Seven Thousand Seven Hundred & Fifty Three and Paise Twenty Five Only
8	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and for all lift 1 cum 114.40	25.60	cum	118.65	3037.44	INR Three Thousand & Thirty Seven and Paise Forty Four Only
9	12 mm cement plaster of mix : 1:6 (1 cement: 6 coarse sand)	35.04	sqm	230.60	8080.22	INR Eight Thousand & Eighty and Paise Twenty Two Only
10	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : 13.61.1 Two or more coats on new work	27.00	sqm	112.30	3032.10	INR Three Thousand & Thirty Two and Paise Ten Only
11	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					334848.88	INR Three Lakh Thirty Four Thousand Eight Hundred & Forty Eight and Paise Eighty Eight Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				