

Validate

Print

Help

Percentage BoQ

Tender Inviting Authority:STAFF OFFICER CIVIL

Name of Work: Cleaning of garland drain and providing hume pipe culvert at JOCP, Hazaribagh Area under monsoon preparation activities 26-27

	Category of Services (To Be Selected by Department)	Category of Bidder(To Be Selected by Bidder)	To Be Entered by Department		
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Item Description/ Heading					
1.01	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth, 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50m and lift up to 1.5m, disposed earth to be levelled and neatly dressed. All kinds of soil	4500.00	Cum	139.70	628650.00	INR Six Lakh Twenty Eight Thousand Six Hundred & Fifty Only
1.02	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	140.00	Cum	205.80	28812.00	INR Twenty Eight Thousand Eight Hundred & Twelve Only
1.03	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size).	7.00	Cum	6773.95	47417.65	INR Forty Seven Thousand Four Hundred & Seventeen and Paise Sixty Five Only

1.04	Laying Reinforced Cement Concrete Pipe NP4/prestressed concrete pipe on first class bedding in single row . (Laying Reinforced cement concrete pipe NP4/prestressed concrete pipe for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets.) 1200 mm dia	25.00	M	9088.75	227218.75	INR Two Lakh Twenty Seven Thousand Two Hundred & Eighteen and Paise Seventy Five Only
1.05	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5 m.	85.05	Cum	118.65	10091.18	INR Ten Thousand & Ninety One and Paise Eighteen Only
1.06	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	25.65	Cum	6770.05	173651.78	INR One Lakh Seventy Three Thousand Six Hundred & Fifty One and Paise Seventy Eight Only
1.07	12 mm cement plaster finished with a floating coat of neat cement of mix : 1:4 (1 cement: 4 fine sand)	133.87	Sqm	303.20	40589.38	INR Forty Thousand Five Hundred & Eighty Nine and Paise Thirty Eight Only
2.00	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					1156430.75	INR Eleven Lakh Fifty Six Thousand Four Hundred & Thirty and Paise Seventy Five Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only					