

Validate

Print

Help

Percentage BoQ

Tender Inviting Authority:STAFF OFFICER CIVIL

Name of Work: Cleaning and cutting of garland drain, hume pipe culvert and 2 nos. shed at various places of mines under TSOCP Hazaribagh Area

	Category of Services (To Be Selected by Department)	Category of Bidder(To Be Selected by Bidder)	To Be Entered by Department		
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Item Description/ Heading					
1.01	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	2090.36	Cum	205.80	430196.09	INR Four Lakh Thirty Thousand One Hundred & Ninety Six and Paise Nine Only
1.02	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size).	1.71	Cum	6773.95	11583.45	INR Eleven Thousand Five Hundred & Eighty Three and Paise Forty Five Only
1.03	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	306.00	Kg	114.90	35159.40	INR Thirty Five Thousand One Hundred & Fifty Nine and Paise Forty Only

1.04	Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %), total coated thickness with zinc coating 120 gm per sqm as per IS:277 in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	57.00	Sqm	698.10	39791.70	INR Thirty Nine Thousand Seven Hundred & Ninety One and Paise Seventy Only
1.05	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work.	13.04	Sqm	112.30	1464.39	INR One Thousand Four Hundred & Sixty Four and Paise Thirty Nine Only
1.06	Providing and laying Non Pressure NP-4 class (Heavy duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete 1200 mm dia RCC pipes. (Laying by manual/ machanical means)	30.00	m	9088.75	272662.50	INR Two Lakh Seventy Two Thousand Six Hundred & Sixty Two and Paise Fifty Only
1.07	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	8.40	Cum	6770.05	56868.42	INR Fifty Six Thousand Eight Hundred & Sixty Eight and Paise Forty Two Only
1.08	12 mm cement plaster finished with a floating coat of neat cement of mix : 1:4 (1 cement: 4 fine sand)	36.00	Sqm	303.20	10915.20	INR Ten Thousand Nine Hundred & Fifteen and Paise Twenty Only
1.09	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5 m.	30.00	Cum	118.65	3559.50	INR Three Thousand Five Hundred & Fifty Nine and Paise Fifty Only
2.00	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					862200.65	INR Eight Lakh Sixty Two Thousand Two Hundred and Paise Sixty Five Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only					