

Validate

Print

Help

**Percentage BoQ**

Tender Inviting Authority:STAFF OFFICER CIVIL

Name of Work: Provision of Hume Pipe Culvert, Cleaning Garland drain and other allied Works for Monsoon Preparation at Tapin North under TNOCP, Hazaribagh Area

	<b>Category of Services (To Be Selected by Department)</b>	<b>Category of Bidder( To Be Selected by Bidder)</b>	<b>To Be Entered by Department</b>		
<b>ITC Available</b>	<b>Works Contract</b>	<b>Bidder's Status (Mandatory)</b>	<b>Rate of GST (in %)</b>	<b>GST to be Paid By Bidder (in Rs.)</b>	<b>GST to be Paid By CIL/Subsidiary (in Rs.)</b>
<b>Name of the Bidder/ Bidding Firm / Company :</b>		<b>Select</b>	<b>18.00</b>	<b>0.00</b>	<b>0.00</b>

**PRICE SCHEDULE**

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

<b>NUMBER #</b>	<b>TEXT #</b>	<b>NUMBER #</b>	<b>TEXT #</b>	<b>NUMBER</b>	<b>NUMBER #</b>	<b>TEXT #</b>
<b>Sl. No.</b>	<b>Item Description</b>	<b>Quantity</b>	<b>Units</b>	<b>Estimated Rate in Rs. P</b>	<b>TOTAL AMOUNT in Rs. P</b>	<b>TOTAL AMOUNT In Words</b>
<b>1</b>	<b>2</b>	<b>3</b>	<b>4</b>	<b>5</b>	<b>6</b>	<b>7</b>
1	<b>Item Description/ Heading</b>					
1.01	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth, 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50m and lift up to 1.5m, disposed earth to be levelled and neatly dressed. All kinds of soil	6297.45	Cum	139.70	<b>879753.77</b>	INR Eight Lakh Seventy Nine Thousand Seven Hundred & Fifty Three and Paise Seventy Six Only
1.02	Providing and laying Reinforced Cement Concrete Pipe NP4/prestssed concrete pipe on first class bedding in single row. (Providing and laying Reinforced cement concrete pipe NP4/prestssed concrete pipe for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets) 1200 mm dia	92.50	metre	9169.00	<b>848132.50</b>	INR Eight Lakh Forty Eight Thousand One Hundred & Thirty Two and Paise Fifty Only
1.03	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size).	24.02	Cum	6773.95	<b>162710.28</b>	INR One Lakh Sixty Two Thousand Seven Hundred & Ten and Paise Twenty Eight Only
1.04	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	45.80	Cum	6770.05	<b>310068.29</b>	INR Three Lakh Ten Thousand & Sixty Eight and Paise Twenty Nine Only
1.05	12 mm cement plaster finished with a floating coat of neat cement of mix : 1:4 (1 cement: 4 fine sand)	134.25	Sqm	303.20	<b>40704.60</b>	INR Forty Thousand Seven Hundred & Four and Paise Sixty Only

1.06	Providing and laying Non Pressure NP-4 class (Heavy duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete 1200 mm dia RCC pipes. (Laying by manual/ machanical means)	89.10	Cum	118.65	10571.72	INR Ten Thousand Five Hundred & Seventy One and Paise Seventy Two Only
2.00	<b>Total impact of GST for the purpose of CTC</b>	1.000	Nos	0.00	0.00	INR Zero Only
<b>Total in Figures</b>					<b>2251941.15</b>	INR Twenty Two Lakh Fifty One Thousand Nine Hundred & Forty One and Paise Fifteen Only
<b>Quoted Rate in Figures</b>			Select		0.00	INR Zero Only
<b>Quoted Rate in Words</b>						<b>INR Zero Only</b>