

**Item Rate BoQ**

<b>Tender Inviting Authority:</b>	Project Engineer (EnM), KOCP, Hazaribagh Area						
<b>Name of the Work / Contract No:</b>	Fabrication of Shed for Pump, Starter and motor at Kedla OCP under Hazaribagh Area.						
<b>Category of Services (To Be Selected by Department)</b>			<b>Category of Bidder (To Be Selected by Bidder)</b>	<b>To Be Entered by Department</b>			
<b>ITC Available</b>	<b>Works Contract</b>	<b>Bidder's Status (Mandatory)</b>	<b>Rate of GST (in %)</b>	<b>Total GST(in Rs.)</b>	<b>GST to be Paid By Bidder (in Rs.)</b>	<b>GST to be Paid By CIL/Subsidiary (in Rs.)</b>	
<b>Name of the Bidder/ Bidding Firm / Company :</b>		Select	18	0.00	0.00	0.00	
<b>PRICE SCHEDULE</b>							
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )							
<b>NUMBER #</b>	<b>TEXT #</b>	<b>NUMBER #</b>	<b>TEXT #</b>	<b>NUMBER</b>	<b>NUMBER #</b>	<b>NUMBER #</b>	<b>TEXT #</b>
<b>Sl. No.</b>	<b>Item Description</b>	<b>Quantity</b>	<b>Units</b>	<b>Estimated Rate in Rs. P</b>	<b>BASIC RATE In Figures To be entered by the Bidder in Rs. P</b>	<b>TOTAL AMOUNT Without Taxes in Rs. P</b>	<b>TOTAL AMOUNT In Words</b>
1	2	3	4	5	6	7	8
1	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	1168.56	Kg			0.00	INR Zero Only
2	Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-Charge) of total coated thickness 0.50mm (base metal of minimum 0.45mm thickness with total coating thickness of 0.05mm) with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	127.50	Sqm			0.00	INR Zero Only
3	providing and fixing mild steel round holding down bolts with nuts and washer plates complete.	70	Kg			0.00	INR Zero Only
4	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and for all lift, as directed by Engineer-in charge. All kinds of soil	2.5	cum			0.00	INR Zero Only
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	4	cum			0.00	INR Zero Only
6	<b>Total impact of GST for the purpose of CTC</b>	1.00	No		0.00	0.00	INR Zero Only
<b>Total in Figures</b>						<b>0.00</b>	INR Zero Only
<b>Quoted Rate in Words</b>	<b>INR Zero Only</b>						