

Validate

Print

Help

Item Rate BoQ

Tender Inviting Authority:	Project Engineer (EnM), KUGP, Hazaribagh Area					
Name of the Work / Contract No:	Towards existing 440 V overhead line and re-erection with supply and fixing of stay/channel, proper earthing and Associated works.					
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P
8	TEXT #	8	TEXT #	8	8	8
1	2	3	4	5	6	7
1	Erection of RCC/ PCC pole of following length in brick ballast and ramming the foundation, finishing with 150mm thick cement concrete (1:3:6) layer on top with including excavation and refilling etc as required Above 8.0 metre and upto 11.0 metre	10	Nos.			0.00
2	Dismantling of pole/ street light standard/ strut embedded in cement concrete foundation etc. as required.	10	Nos.			0.00
3	Erection of all aluminium conductor of 7/1.96 mm to 7/3.10 mm diameter including binding etc. as required.	460.8	Kg			0.00
4	Supply of Channel iron 75mm x 40mm x 6mm (7.14Kg/mtr) cross arm for 4 wire OH Line complete with clamps, bolts, nuts and washer etc. including drilling of holes for insulators pins etc. (as per drawing) and painting with primer and finished paint as required.	16	Set			0.00
5	Erection of Angle iron/channel cross arm on wooden/RCC/PCC/Steel tubular/Rail Poles etc as required.	20	Set			0.00
6	Supplying & erection of stay set complete (galvanized) with 19/20 mm dia x 1.8 Mtr long stay rod anchor plate of size 45cm x 45cm x 7.5 mm thimble stay clamp turn buckle (20mm x 60cm) 7/4.00 mm dia G.I. wire and strain Insulator etc in cement concrete (1cement: 3coarse sand: 6 graded stone aggregate 40mm nominal size) foundation including excavation & refilling etc. as required.	8	Nos.			0.00
7	Dismantling of over head lines comprising of copper/ aluminium over head conductor, G.I. wire, cross arms, insulators etc. as required.	460.80	Kg			0.00
8	Total impact of GST for the purpose of CTC	1.00	No		0.00	0.00
Total in Figures						0.00
Quoted Rate in Words	INR Zero Only					