

Validate

Print

Help

Tender Inviting Authority: Staff Officer(Civil), NK Area.

Name of Work: Preparation of Garland Drain along Mine Boundary (1000 Mtrs) Cleaning of Existing Drain (4250 Mtrs) of Rohini Mines and Provision of .3 Nos. culvert with Hume Pipe in 3 different places of Mines area of Rohini Project under Rohini Project NK Area."

	<b>Category of Services (To Be Selected by Department)</b>	<b>Category of Bidder (To Be Selected by Bidder)</b>	<b>To Be Entered by Department</b>		
<b>ITC Available</b>	<b>Works Contract</b>	<b>Bidder's Status (Mandatory)</b>	<b>Rate of GST (in %)</b>	<b>GST to be Paid By Bidder (in Rs.)</b>	<b>GST to be Paid By CIL/Subsidiary (in Rs.)</b>
<b>Name of the Bidder/ Bidding Firm / Company :</b>		<b>Select</b>	<b>18.00</b>	<b>0.00</b>	<b>0.00</b>

**PRICE SCHEDULE**

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	<b>PART-A ( Preparation of Garland Drain along mine Boundary (1000mts) of Rohini Mines)</b> Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and for all lift, as directed by Engineer-in-charge.All kinds of soil.	2700.00	Cum	139.7	377190.00	INR Three Lakh Seventy Seven Thousand One Hundred & Eighty Nine and Paise One Hundred Only
2	<b>PART-B (Cleaning of existing Drain (4250.00 mts) of Rohini Mines)</b> Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and for all lift, as directed by Engineer-in-charge.All kinds of soil.	11475.00	Cum	139.70	1603057.50	INR Sixteen Lakh Three Thousand & Fifty Seven and Paise Fifty Only
3	<b>PART-C- (Provision of 3nos culvert with Hume pipe in 3 different places of mines area of Rohini Project)</b> Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.All kinds of soil.	400.50	Cum	205.80	82422.90	INR Eighty Two Thousand Four Hundred & Twenty Two and Paise Ninety Only
4	Extra for every additional lif of 1.5 m or part thereof in excavation / banking excavated or stacked materials.All kinds of soil.	200.25	Cum	76.45	15309.11	INR Fifteen Thousand Three Hundred & Nine and Paise Eleven Only
5	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	115.77	Cum	1438.1	166488.84	INR One Lakh Sixty Six Thousand Four Hundred & Eighty Eight and Paise Eighty Four Only

6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources: 8 graded stone aggregate 40 mm nominal size derived from natural sources).	26.70	Cum	6072.40	162133.08	INR One Lakh Sixty Two Thousand One Hundred & Thirty Three and Paise Eight Only
7	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:Cement mortar 1:6(1 cement :6 coarse sand).	39.36	Cum	6770.05	266461.04	INR Two Lakh Sixty Six Thousand Four Hundred & Sixty One and Paise Four Only
8	12 mm cement plaster finished with a floating coat of neat cement of mix:1:4(1 cement: 4 fine sand).	125.82	Sqm	303.2	38147.90	INR Thirty Eight Thousand One Hundred & Forty Seven and Paise Ninety Only
9	Providing and laying Non Pressure NP-4 class (Heavy duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete. 1200 mm dia RCC pipes. (Laying by manual/ machanical means).	75.00	Meter	9088.75	681656.25	INR Six Lakh Eighty One Thousand Six Hundred & Fifty Six and Paise Twenty Five Only
10	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 and for all lift.	133.89	Cum	118.65	15886.05	INR Fifteen Thousand Eight Hundred & Eighty Six and Paise Five Only
11	<b>Total impact of GST for the purpose of CTC</b>	1.000	Nos	0.00	0.00	INR Zero Only
<b>Total in Figures</b>					<b>3408752.67</b>	INR Thirty Four Lakh Eight Thousand Seven Hundred & Fifty Two and Paise Sixty Seven Only
<b>Quoted Rate in Figures</b>			<b>Select</b>		<b>0.00</b>	INR Zero Only
<b>Quoted Rate in Words</b>	<b>INR Zero Only</b>					