

Validate

Print

Help

Tender Inviting Authority: Staff Officer(Civil), NK Area.

Name of Work: Cleaning of 1000 meters of garland drain, Drain cutting of 750 Meters, Construction of Pillar for dump stability and Construction of a pump foundation at Purnadih Project under Purnadih Project,NK Area.

| | | | | | |
|---|--|--|------------------------------------|--|--|
| | Category of Services (To Be Selected by Department) | Category of Bidder (To Be Selected by Bidder) | To Be Entered by Department | | |
| ITC Available | Works Contract | Bidder's Status (Mandatory) | Rate of GST (in %) | GST to be Paid By Bidder (in Rs.) | GST to be Paid By CIL/Subsidiary (in Rs.) |
| Name of the Bidder/ Bidding Firm / Company : | | Select | 18.00 | 0.00 | 0.00 |

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

| NUMBER # | TEXT # | NUMBER # | TEXT # | NUMBER | NUMBER # | TEXT # |
|----------|---|----------|--------|-------------------------|-----------------------|---|
| Sl. No. | Item Description | Quantity | Units | Estimated Rate in Rs. P | TOTAL AMOUNT in Rs. P | TOTAL AMOUNT in Words |
| 1 | 2 | 3 | 4 | 5 | 6 | 7 |
| 1 | Part-A Cleaning of 1000 meters of garland drain along mine boundary) Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.All kinds of soil. | 2700.00 | Cum | 205.8 | 555660.00 | INR Five Lakh Fifty Five Thousand Six Hundred & Sixty Only |
| 2 | Part-B Drain cutting (New) of 700 meters) Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.All kinds of soil. | 2025.00 | Cum | 205.80 | 416745.00 | INR Four Lakh Sixteen Thousand Seven Hundred & Forty Five Only |
| 3 | Part-C Construction of pillar for dump stability at Purnadih Project) Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15 degree landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources). | 4.56 | Cum | 9824.55 | 44799.95 | INR Forty Four Thousand Seven Hundred & Ninety Nine and Paise Ninety Five Only |
| 4 | Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc. for mass concrete | 40.50 | Sqm | 277.90 | 11254.95 | INR Eleven Thousand Two Hundred & Fifty Four and Paise Ninety Five Only |
| 5 | Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more. | 364.80 | Kg | 105.6 | 38522.88 | INR Thirty Eight Thousand Five Hundred & Twenty Two and Paise Eighty Eight Only |

| | | | | | | |
|-------------------------------|--|--------|---------------|-------------|-------------------|--|
| 6 | Part-D Pump foundation (one nos) Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil. | 0.32 | Cum | 205.80 | 65.86 | INR Sixty Five and Paise Eighty Six Only |
| 7 | Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. All kinds of soil | 20.00 | Sqm | 20.50 | 410.00 | INR Four Hundred & Ten Only |
| 8 | Supplying and filling in plinth with sand under floors, including watering, | 2.00 | Cum | 1438.1 | 2876.20 | INR Two Thousand Eight Hundred & Seventy Six and Paise |
| 9 | Dry brick pitching half brick thick in drains including supply of bricks and preparing the surface complete : With common burnt clay F.P.S. (non modular) bricks of class designation 7.5 | 20.00 | Sqm | 675.7 | 13514.00 | INR Thirteen Thousand Five Hundred & Fourteen Only |
| 10 | Providing and laying in position cement concrete of specified grade | 0.32 | Cum | 7149.05 | 2287.70 | INR Two Thousand Two Hundred & Eighty Seven and Paise |
| 11 | Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3(1 cement: 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources) | 1.69 | Cum | 8343.45 | 14100.43 | INR Fourteen Thousand One Hundred and Paise Forty Three Only |
| 12 | Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more. Thermo-Mechanically Treated bars of grade Fe-500D or more. | 169.00 | Kg | 105.60 | 17846.40 | INR Seventeen Thousand Eight Hundred & Forty Six and Paise Forty Only |
| 13 | Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. | 798.56 | Kg | 114.90 | 91754.54 | INR Ninety One Thousand Seven Hundred & Fifty Four and Paise Fifty Four Only |
| 14 | Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-Charge) of total coated thickness 0.50 mm (base metal of minimum 0.45 mm thickness with total coating thickness of 0.05mm) with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. | 26.66 | Sqm | 698.10 | 18611.35 | INR Eighteen Thousand Six Hundred & Eleven and Paise Thirty Five Only |
| 15 | Extra for providing and fixing wind ties of 40x 6 mm flat iron section. | 33.60 | Meter | 175.35 | 5891.76 | INR Five Thousand Eight Hundred & Ninety One and Paise Seventy Six Only |
| 16 | Providing and fixing pre-coated galvanised steel sheet roofing accessories of total coated thickness 0.50 mm (base metal of minimum 0.45 mm thickness with total coating thickness of 0.05 mm) with Zinc coating 120 gram per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws complete : Ridges plain (500- 600mm) | 5.60 | Meter | 637.93 | 3572.41 | INR Three Thousand Five Hundred & Seventy Two and Paise Forty One Only |
| 17 | Total impact of GST for the purpose of CTC | 1.000 | Nos | 0.00 | 0.00 | INR Zero Only |
| Total in Figures | | | | | 1237913.42 | INR Twelve Lakh Thirty Seven Thousand Nine Hundred & Thirteen and Paise Forty Two Only |
| Quoted Rate in Figures | | | Select | | 0.00 | INR Zero Only |
| Quoted Rate in Words | INR Zero Only | | | | | |

