

Tender Inviting Authority: Staff Officer(Civil), Rajhara Area.						
Name of Work:Cutting and Cleaning of Catch drain and sump arrangement around OB dump and Laying of hume pipes at different locations at ROCP under Rajhara Area.						
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00	
<b>PRICE SCHEDULE</b>						
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )						
<b>NUMBER #</b>	<b>TEXT #</b>	<b>NUMBER #</b>	<b>TEXT #</b>	<b>NUMBER</b>	<b>NUMBER #</b>	<b>TEXT #</b>
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30cm in depth, 1.5 min width as well as 1.0sqm on plan) including getting out and disposal of excavated earth upto 50m and for all lift, as directed by Engineer-in-charge. 2.6.1 All kinds of soil 1 cum 12B.05	2183.40	cum	139.70	305020.98	INR Three Lakh Five Thousand & Twenty and Paise Ninety Eight Only
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and for all lift	43.20	cum	118.65	5125.68	INR Five Thousand One Hundred & Twenty Five and Paise Sixty Eight Only
3	Providing and laying Non-Pressure NP-4 class (Heavy duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joint setc. complete complete 1200 mm dia RCC pipes. (Laying by manual/ machanical means) metre 8117.60	40.00	m	9088.75	363550.00	INR Three Lakh Sixty Three Thousand Five Hundred & Fifty Only
4	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					673696.66	INR Six Lakh Seventy Three Thousand Six Hundred & Ninety Six and Paise Sixty Six Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words						INR Zero Only