

Validate		Print		Help		Percentage BoQ	
Tender Inviting Authority: Staff Officer (Civil),CCL, Dhori Area							
Name of Work:- Filling of earth and other minor miscellaneous works near 05 no. Dhowrah for fire Containment under AADOCM of Dhori Area.							
Category of Services (To Be Selected by Department)		Category of Bidder(To Be Selected by Bidder)		To Be Entered by Department			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)		
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00		
PRICE SCHEDULE							
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)							
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #	
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT in Words	
1	2	3	4	5	6	7	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and for all lift, as directed by Engineer-in-charge All kinds of soil	5802	cum	139.70	810539.40	INR Eight Lakh Ten Thousand Five Hundred & Thirty Nine and Paise Forty Only	
2	Carriage of materialBy Mechanical Transport including loading,unloading and stacking Earth Lead - 5 km	5802	cum	224.10	1300228.20	INR Thirteen Lakh Two Hundred & Twenty Eight and Paise Twenty Only	
3	Filling available excavated earth (excluding rock) in trenches, plinth. sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and for all lift	5802	cum	118.65	688407.30	INR Six Lakh Eighty Eight Thousand Four Hundred & Seven and Paise Thirty Only	
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources: 4 graded stone aggregate 20 mm nominal size derived from natural sources)	5.8	cum	7424.45	43061.81	INR Forty Three Thousand & Sixty One and Paise Eighty One Only	
5	Retro- reflectorised Traffic signs (Providing and fixing of retro-reflectorised cautionary, mandatory and informatory sign as per IRC :67 made of encapsulated lens type reflective sheeting vide clause 801.3, fixed over aluminium sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm x 75 mm x 6 mm firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 45 cm x 45 cm x 60 cm, 60 cm below ground level as per approved drawing) 90 cm equilateral triangle	2	Nos	7240	14480.00	INR Fourteen Thousand Four Hundred & Eighty Only	
6	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only	
Total in Figures					2856716.71	INR Twenty Eight Lakh Fifty Six Thousand Seven Hundred & Sixteen and Paise Seventy One Only	
Quoted Rate in Figures					0.00	INR Zero Only	
		Select					

Quoted Rate in Words

INR Zero Only