

Bill of Quantity

Name of Work: "Extension of 3.3KV HT overhead line for pump installation on out sourcing patch at Rajhara Colliery under Rajhara Area"

Sl.No.	Description	Qty.	Unit	Rate(Rs.)	Total(Rs.)
1.	Erection of metallic pole of following length in cement concrete 1:3:6 foundation including excavation and refilling etc. as required. Above 1 1.0 meter and up to 12.0 meter	20.00	Nos.		
2.	Erection of ACSR conductor for 3.3kV overhead line.	360.00	Kg		
3.	Repairing and erection of galvanized stay set for 3.3 KV overhead lines	8.00	Set		
4.	Erection of 3.3KV disc/ pin insulator	60.00	Set		
5.	Erection of pole top/ straight two wire/ V shape two wire, angle iron/ channel , cross arm on steel poles	12.00	Set		
6.	Erection of double pole 3 wire cross arm for 1 1KV/22KV/ 33KV overhead lines as required.	8.00	Set		
Sub Total					
GST@18%					
Total					
Total In Words					

Project Engineer (E&M)
Rajhara GCP

I accept all terms and conditions of NIQ.

Signature of the bidder: