

Bill of Quantity

Name of Work: "Repair of outdoor VCB switch rated-3.3KV, SIno-SP/O/2165, make-EEL at Rajhara Colliery under Rajhara Area"

Sl.No.	Description	Qty.	Unit	Rate(Rs.)	Total(Rs.)
1.	Repairing of Mechanism	1.00	AU		
2.	Providing and denting cleaning and double coat painting	1.00	AU		
3.	Providing wiring including materials PVC copper,wire lug,ferrule tie,belt etc. of VCBswitch.	1.00	AU		
4.	Providing Rectifier mechanism	1.00	NOS.		
5.	Providing Earth leakage relay digital type with CBCT	1.00	NOS.		
6.	Providing Tripping/closing coil assembly 110volt DC	2.00	NOS.		
7.	Providing Support insulator 3.3KV grade	12.00	NOS.		
8.	Providing Bolt, nut and washer	5	KG		
9.	Providing TNC switch for electric operated VCB	1.00	NOS		
10.	Providing Ampere/voltmeter selector switch	2.00	NOS		
11.	Providing Indicating Lamp LED 110Volt	6.00	NOS		
12.	Providing P.T.fuse 3 Ampere ,3.3KV	3.00	NOS		
13.	Providing Auxiliary connector 2NO+2NC,110Volt	1.00	NOS		
14.	Providing Ampere meter digital type	1.00	NOS.		
15.	Providing HT bushing with stud nut & washer complete set	2.00	NOS		
16.	Fixing charges @15% from Sl.No.-04 to 15	1.00	AU		
Sub Total					
GST@18%					
Total					
Total In Words					

Project Engineer (E&M)

Rajhara OCP

I accept all terms and conditions of NIQ.

Signature of the bidder: