

Validate

Print

Help

Tender Inviting Authority: Staff Officer(Civil), NK Area.

Name of Work:-Construction of 40 nos. (12 nos. bricks &amp; 28 RCC) permanent &amp; preparatory sectionalisation stopping to sectionalize around panel no W6,W7,W8,W9 of lower Bachra seam and Benti Block (Main Dip-2 Panel B5 &amp; West panel-1) in Lower Bachra Seam under Churi Colliery ,NK Area

	<b>Category of Services (To Be Selected by Department)</b>	<b>Category of Bidder (To Be Selected by Bidder)</b>	<b>To Be Entered by Department</b>		
<b>ITC Available</b>	<b>Works Contract</b>	<b>Bidder's Status (Mandatory)</b>	<b>Rate of GST (in %)</b>	<b>GST to be Paid By Bidder (in Rs.)</b>	<b>GST to be Paid By CIL/Subsidiary (in Rs.)</b>
<b>Name of the Bidder/ Bidding Firm / Company :</b>		<b>Select</b>	<b>18.00</b>	<b>0.00</b>	<b>0.00</b>

**PRICE SCHEDULE**

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.Ordinary rock	324.80	Cum	988.55	<b>321081.04</b>	INR Three Lakh Twenty One Thousand & Eighty One and Paise Four Only
2	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: cement mortar 1:6(1 cement :6 coarse sand)	79.20	Cum	9662.82	<b>765295.34</b>	INR Seven Lakh Sixty Five Thousand Two Hundred & Ninety Five and Paise Thirty Four Only
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6(1 cement : 6 coarse sand)	168.00	Cum	12986.86	<b>2181792.48</b>	INR Twenty One Lakh Eighty One Thousand Seven Hundred & Ninety Two and Paise Forty Eight Only
4	Centering and shuttering including strutting, propping etc. and removal of form for Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	1411.20	Sqm	1282.89	<b>1810414.37</b>	INR Eighteen Lakh Ten Thousand Four Hundred & Fourteen and Paise Thirty Seven Only
5	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3(1 cement: 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	88.20	Cum	11944.26	<b>1053483.73</b>	INR Ten Lakh Fifty Three Thousand Four Hundred & Eighty Three and Paise Seventy Three Only

6	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement:1:1.5:3 (1 cement : 1.5 coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	205.80	Cum	14954.03	3077539.37	INR Thirty Lakh Seventy Seven Thousand Five Hundred & Thirty Nine and Paise Thirty Seven Only
7	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	10027.14	kg	127.90	1282471.21	INR Twelve Lakh Eighty Two Thousand Four Hundred & Seventy One and Paise Twenty One Only
8	12 mm cement plaster of mix : 1:6(1 cement: 6 fine sand)	151.20	sqm	511.82	77387.18	INR Seventy Seven Thousand Three Hundred & Eighty Seven and Paise Eighteen Only
9	6 mm cement plaster of mix:1:3 (1 cement : 3 fine sand )	1411.20	sqm	463.96	654740.35	INR Six Lakh Fifty Four Thousand Seven Hundred & Forty and Paise Thirty Five Only
10	Satna lime wash on walls with one coat .	705.60	sqm	24.15	17040.24	INR Seventeen Thousand & Forty and Paise Twenty Four Only
11	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade two or more coats on new work	19.67	sqm	238.29	4687.16	INR Four Thousand Six Hundred & Eighty Seven and Paise Sixteen Only
12	Providing and fixing GI Pipes ,40 mm dia	32.00	m	443.10	14179.20	INR Fourteen Thousand One Hundred & Seventy Nine and Paise Twenty Only
13	Supply of Bricks	115690.00	nos	8.34	964854.60	INR Nine Lakh Sixty Four Thousand Eight Hundred & Fifty Four and Paise Sixty Only
14	Supply of coarse sand (Zone-III)	77.00	cum	1,276.50	98290.50	INR Ninety Eight Thousand Two Hundred & Ninety and Paise Fifty Only
15	Supply of stone aggregates (20 mm nominal size)	6.00	cum	2864.94	17189.64	INR Seventeen Thousand One Hundred & Eighty Nine and Paise Sixty Four Only
16	Carriage of materials by manual labour including loading ,unloading and stacking for less than 0.50 km (average lead =50m) Cost per unit for 1st 50 m Bricks in Nos.	237807.00	nos	0.92	218782.44	INR Two Lakh Eighteen Thousand Seven Hundred & Eighty Two and Paise Forty Four Only
17	Cost per unit for 1st 50 m Aggregate in cum	523.98	cum	494.85	259291.50	INR Two Lakh Fifty Nine Thousand Two Hundred & Ninety One and Paise Fifty Only
18	Cost per unit for 1st 50 m Cement in Te	133.00	Te	286.60	38117.80	INR Thirty Eight Thousand One Hundred & Seventeen and Paise Eighty Only
19	Semiskilled labour required for transportation of tubs ( bricks, sand ,cement ) & manual labour including loading ,unloading avg.distance =(4+2)/2 =3.0km Bricks in nos.	237807.00	nos	4.56	1084399.92	INR Ten Lakh Eighty Four Thousand Three Hundred & Ninety Nine and Paise Ninety Two Only
20	Stone aggregate, sand & cement in cum	616.00	cum	1614.70	994655.20	INR Nine Lakh Ninety Four Thousand Six Hundred & Fifty Five and Paise Twenty Only
21	<b>Total impact of GST for the purpose of CTC</b>	1.000	Nos	<b>0.00</b>	<b>0.00</b>	INR Zero Only
<b>Total in Figures</b>					<b>14935693.29</b>	INR One Crore Forty Nine Lakh Thirty Five Thousand Six Hundred & Ninety Three and Paise Twenty Nine Only
<b>Quoted Rate in Figures</b>			Select		<b>0.00</b>	INR Zero Only
<b>Quoted Rate in Words</b>	<b>INR Zero Only</b>					