

Validate

Print

Help

## Percentage BoQ

Tender Inviting Authority: Staff Officer(Civil), Magadh-Sanghmitra Area

Name of Work : Repair &amp; maintenance of quarter no. D-01 at Sur Vihar Colony under GM Unit of Magadh-Sanghmitra Area. (e NIT No. 06 of 2026-27)

	<b>Category of Services (To Be Selected by Department)</b>	<b>Category of Bidder( To Be Selected by Bidder)</b>	<b>To Be Entered by Department</b>		
<b>ITC Not Available</b>	<b>Works Contract</b>	<b>Bidder's Status (Mandatory)</b>	<b>Rate of GST (in %)</b>	<b>GST to be Paid By Bidder (in Rs.)</b>	<b>GST to be Paid By CIL/Subsidiary (in Rs.)</b>
<b>Name of the Bidder/ Bidding Firm / Company :</b>		<b>Select</b>	<b>18.00</b>	<b>0.00</b>	<b>0.00</b>

## PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.:For thickness of tiles 10 mm to 25 mm	7.95	sqm	45.40	360.93	INR Three Hundred & Sixty and Paise Ninety Three Only
2	Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50 metres lead.	11.00	each	116.70	1283.70	INR One Thousand Two Hundred & Eighty Three and Paise Seventy Only
3	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains not exceeding 1.5 m in width or 10 sqm on plan including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed within a lead of 50m. All kinds of soil	2.36	cum	205.80	485.69	INR Four Hundred & Eighty Five and Paise Sixty Nine Only
4	Supplying and filling in plinth with Jamuna sand under floors, including watering, ramming, consolidating and dressing complete.	0.19	cum	1438.10	273.24	INR Two Hundred & Seventy Three and Paise Twenty Four Only
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	0.38	cum	6072.40	2307.51	INR Two Thousand Three Hundred & Seven and Paise Fifty One Only
6	Brick work with F.P.S. bricks of class designation 50 in foundation and plinth in :Cement mortar 1:6 (1 cement : 6 coarse sand)	0.64	cum	6770.05	4332.83	INR Four Thousand Three Hundred & Thirty Two and Paise Eighty Three Only
7	Brick work with F.P.S. bricks of class designation 5.0 in superstructure above plinth level upto floor V level in all shapes and sizes in :Cement mortar 1:6 (1 cement : 6 coarse sand)	0.28	cum	7988.95	2236.91	INR Two Thousand Two Hundred & Thirty Six and Paise Ninety One Only
8	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30cm in depth. 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m, disposed earth to be levelled and neatly dressed.	1.75	cum	139.70	244.48	INR Two Hundred & Forty Four and Paise Forty Seven Only
9	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	1.05	cum	7424.45	7795.67	INR Seven Thousand Seven Hundred & Ninety Five and Paise Sixty Seven Only
10	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS : 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600x600 mm	7.20	sqm	1385.20	9973.44	INR Nine Thousand Nine Hundred & Seventy Three and Paise Forty Four Only
11	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	51.37	sqm	1131.60	58130.29	INR Fifty Eight Thousand One Hundred & Thirty and Paise Twenty Nine Only

12	12 mm cement plaster of mix :1:6 (1 cement : 6 fine sand)	202.19	sqm	230.60	<b>46625.01</b>	INR Forty Six Thousand Six Hundred & Twenty Five and Paise One Only
13	Dry brick on edge flooring in required pattern with bricks of class designation 50 on a bed of 12 mm mud mortar including filling joints with Jamuna sand (with F.P.S. bricks) complete.	89.37	sqm	767.25	<b>68569.13</b>	INR Sixty Eight Thousand Five Hundred & Sixty Nine and Paise Thirteen Only
14	Chequerred precast cement concrete tiles 22 mm thick in footpath & courtyard, jointed with neat cement slurry mixed with pigment to match the shade of tiles, including rubbing and cleaning etc. complete, on 20 mm thick bed of cement mortar 1:4 (1 cement: 4 coarse sand). Medium shade pigment using 50% white cement 50% Grey cement	89.37	sqm	988.05	<b>88302.03</b>	INR Eighty Eight Thousand Three Hundred & Two and Paise Three Only
15	12 mm cement plaster finished with a floating coat of neat cement of mix :1:4 (1 cement : 4 fine sand)	8.00	sqm	303.20	<b>2425.60</b>	INR Two Thousand Four Hundred & Twenty Five and Paise Sixty Only
16	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	777.81	kg	114.90	<b>89370.37</b>	INR Eighty Nine Thousand Three Hundred & Seventy and Paise Thirty Seven Only
17	Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm +/- 5% total coated thickness (TCT), zinc coating 120gms as per IS: 277 in 240mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches while transportation and should be supplied in length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling / self tapping screws of size (50x55mm) with EPDM seal or with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead complete upto any pitch in horizontal/ vertical or curved surfaces excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	84.70	sqm	698.10	<b>59129.07</b>	INR Fifty Nine Thousand One Hundred & Twenty Nine and Paise Seven Only
18	Extra for providing and fixing wind ties of 40x 6mm flat iron section	66.60	metre	175.35	<b>11678.31</b>	INR Eleven Thousand Six Hundred & Seventy Eight and Paise Thirty One Only
19	Providing, hoisting and fixing upto floor five level precast reinforced cement concrete work in string courses, bands, copings, bed plates, anchor blocks, plain window sills and the like including the cost of required centring, shuttering, finishing smooth with 6mm thick cement plaster 1:3 (1 cement :3 fine sand) on exposed surfaces complete but excluding cost of reinforcement with 1:2:4 (1cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size).	0.54	cum	9432.95	<b>5093.79</b>	INR Five Thousand & Ninety Three and Paise Seventy Nine Only
20	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars	43.20	kg	105.60	<b>4561.92</b>	INR Four Thousand Five Hundred & Sixty One and Paise Ninety Two Only
21	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 5.0 in foundations and plinth in. Cement mortar 1:4 (1 cement : 4 coarse sand)	12.12	sqm	844.15	<b>10231.10</b>	INR Ten Thousand Two Hundred & Thirty One and Paise Ten Only
22	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/appropriate Z sections and other sections of approved make conforming to IS: 733 and IS : 1285, fixed with rawl plugs and screws or with fixing clips, or with expansion hold fasteners including necessary filling up of gaps at junctions, at top, bottom and sides with required PVC/neoprene felt etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / panelling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing and panelling to be paid for separately.): For fixed portion. Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868. minimum anodic coating of grade AC 15)	18.80	kg	528.30	<b>9932.04</b>	INR Nine Thousand Nine Hundred & Thirty Two and Paise Four Only
23	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For shutters of doors, windows & ventilators including providing and fixing hinges / pivots and making provision for fixing of fittings wherever required including the cost of PVC / neoprene gasket required (Fittings shall be paid for separately.); Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868. minimum anodic coating of grade AC 15)	45.44	kg	596.55	<b>27107.23</b>	INR Twenty Seven Thousand One Hundred & Seven and Paise Twenty Three Only
24	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	193.64	sqm	114.95	<b>22258.92</b>	INR Twenty Two Thousand Two Hundred & Fifty Eight and Paise Ninety Two Only

25	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings including fixing the pipe with clamps at 1.00 metre spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling and testing of joints complete as per direction of the Engineer-in-charge.External work :25 mm nominal outer dia pipes.	20.00	metre	298.00	<b>5960.00</b>	INR Five Thousand Nine Hundred & Sixty Only
26	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings including fixing the pipe with clamps at 1.00 metre spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling and testing of joints complete as per direction of the Engineer-in-charge.External work.:20 mm nominal outer dia pipes.	15.00	metre	235.95	<b>3539.25</b>	INR Three Thousand Five Hundred & Thirty Nine and Paise Twenty Five Only
27	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings including fixing the pipe with clamps at 1.00 metre spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of the Engineer-in-charge.:Concealed work including cutting chases and making good the wall etc.:15 mm nominal outer dia pipes	15.00	metre	366.40	<b>5496.00</b>	INR Five Thousand Four Hundred & Ninety Six Only
28	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound ) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. One coat	347.21	Sqm	69.10	<b>23992.21</b>	INR Twenty Three Thousand Nine Hundred & Ninety Two and Paise Twenty One Only
29	Finishing walls with water proofing cement paint of required shade : Old work (one or more coats @ 2.20 kg/10 sqm) complete.	755.88	sqm	52.00	<b>39305.76</b>	INR Thirty Nine Thousand Three Hundred & Five and Paise Seventy Six Only
30	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	110.02	sqm	73.40	<b>8075.47</b>	INR Eight Thousand & Seventy Five and Paise Forty Seven Only
31	Painting with synthetic enamel paint : Two or more coats on new work	132.99	sqm	112.30	<b>14934.78</b>	INR Fourteen Thousand Nine Hundred & Thirty Four and Paise Seventy Eight Only
32	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with PVC / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item.) :With float glass panes of 4.0 mm thickness	5.46	sqm	921.75	<b>5032.76</b>	INR Five Thousand & Thirty Two and Paise Seventy Six Only
33	Providing and fixing 19mm thick both side balancing lamination factory pressed BWP grade marine ply as per IS 710 of approved brand boxes, shelves, racks, almirah, cupboard and drawer etc. including necessary nails,screws etc. complete as per direction of Engineer-in-charge.	11.82	sqm	2111.05	<b>24952.61</b>	INR Twenty Four Thousand Nine Hundred & Fifty Two and Paise Sixty One Only
34	Providing & Fixing decorative high pressure laminated sheet of plain / wood grain in gloss / matt/ suede finish with high density protective surface layer and reverse side of adhesive bonding quality conforming to IS : 2046 Type S, including cost of adhesive of approved quality. 1.0 mm thick	10.66	sqm	847.55	<b>9034.88</b>	INR Nine Thousand & Thirty Four and Paise Eighty Eight Only
35	Providing and fixing ISI marked flush door shutters conforming to IS: 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters.:35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws.	13.30	sqm	1920.05	<b>25536.67</b>	INR Twenty Five Thousand Five Hundred & Thirty Six and Paise Sixty Seven Only
36	Providing and fixing nickel plated M.S. pipe curtain rods with nickel plated brackets : 25 mm dia (heavy type)	8.00	sqm	142.20	<b>1137.60</b>	INR One Thousand One Hundred & Thirty Seven and Paise Sixty Only
37	Supplying C.P. angle Cock With Wall flange for basin mixer and geyser points 15 mm nominal bore (Jaquar or its equivalent) all complete as per instruction of EIC.	8.00	no	1133.62	<b>9068.96</b>	INR Nine Thousand & Sixty Eight and Paise Ninety Six Only
38	Supplying Wall mixer 3 in 1 With Wall flange (Jaquar or its equivalent) as per instruction of EIC.	2.00	no	6849.37	<b>13698.74</b>	INR Thirteen Thousand Six Hundred & Ninety Eight and Paise Seventy Four Only
39	Supply of Stainless steel Towel Rack 600 mm (Jaquar or its equivalent) all complete as per instruction of EIC.	2.00	no	4967.74	<b>9935.48</b>	INR Nine Thousand Nine Hundred & Thirty Five and Paise Forty Eight Only
40	Supply of Central Hole Basin Mixer without Popup Waste System with 450mm Long Braided Hoses (Jaquar or its equivalent) all complete as instruction of EIC.	3.00	no	3280.08	<b>9840.24</b>	INR Nine Thousand Eight Hundred & Forty and Paise Twenty Four Only
41	Supply of Single Lever Basin Mixer without Popup Waste with 450mm Long Braided Hoses (Jaquar or its equivalent) all complete as per instruction of EIC.	2.00	no	3569.43	<b>7138.86</b>	INR Seven Thousand One Hundred & Thirty Eight and Paise Eighty Six Only
42	Supplying wash basin with Pedestal White Vitreous China Flat back wash basin size 590x490x185 mm (Jaquar or its equivalent) all complete as per instruction of EIC.	4.00	no	6583.38	<b>26333.52</b>	INR Twenty Six Thousand Three Hundred & Thirty Three and Paise Fifty Two Only
43	Supply of Sink mixer (wall mounted) with 150 mm long swivel spout, connecting leg and wall flanges (Jaquar or equivalent) all complete as per instruction of EIC.	1.00	no	4920.11	<b>4920.11</b>	INR Four Thousand Nine Hundred & Twenty and Paise Eleven Only
44	Supply of two way bib cock with wall flange (Jaquar or equivalent) complete as per instruction of EIC.	2.00	no	1978.03	<b>3956.06</b>	INR Three Thousand Nine Hundred & Fifty Six and Paise Six Only
45	Supply of overhead shower 100mm dia round shape single flow (ABS body chrome plated with gray face plate) with rubit cleaning system and shower arm casted 190 mm long light body round shape for wall mounted showers with wall flange ( JAQUAR or equivalent) all complete as per instruction of EIC.	2.00	no	1494.85	<b>2989.70</b>	INR Two Thousand Nine Hundred & Eighty Nine and Paise Seventy Only

46	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40mm flush bend, over-flow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete including painting of fittings and brackets, cutting and making good the walls and floors wherever required.:W.C. pan with ISI marked white solid plastic seat and lid.	2.00	each	5889.05	<b>11778.10</b>	INR Eleven Thousand Seven Hundred & Seventy Eight and Paise Ten Only
47	Providing and fixing PTMT soap Dish Holder having length of 138mm, breadth 102mm, height of 75mm with concealed fitting arrangements, weighing not less than 106 gms.	4.00	each	157.75	<b>631.00</b>	INR Six Hundred & Thirty One Only
48	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete 32 mm dia	4.00	each	85.30	<b>341.20</b>	INR Three Hundred & Forty One and Paise Twenty Only
49	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm, for doors, windows and clerestory windows with hinges and necessary screws :30 mm thick shutters Kiln seasoned and chemically treated hollock wood	4.31	sqm	2550.85	<b>10994.16</b>	INR Ten Thousand Nine Hundred & Ninety Four and Paise Sixteen Only
50	Providing and fixing ISI marked oxidised M.S. sliding door bolts with nuts and screws etc. complete : 250x16 mm	14.00	each	142.95	<b>2001.30</b>	INR Two Thousand & One and Paise Thirty Only
51	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 75 mm	14.00	each	45.75	<b>640.50</b>	INR Six Hundred & Forty and Paise Fifty Only
52	Providing and fixing PTMT towel ring trapezoidal shape 215mm long, 200mm wide with a minimum distances of 37mm from wall face with concealed fittings arrangement of approved quality colour, weighing not less than 88 gms.	2.00	each	240.95	<b>481.90</b>	INR Four Hundred & Eighty One and Paise Ninety Only
53	Providing & laying Selection no. 1 doob grass turf with earth 50mm to 60mm thickness of existing ground prepared with proper level and ramming with required tools wooden and than rolling the surface with light roller make the surface smoothen and light watering the same maintenance for 30 days or more till the grass establish properly, as per direction of officer in charge	289.46	Per Sqm	86.20	<b>24951.45</b>	INR Twenty Four Thousand Nine Hundred & Fifty One and Paise Forty Five Only
54	Providing and displaying of Aglaonema Butterfly having ht.30 cm 10 to 12 fresh, healthy and attractive colorful leaves, well developed in 25 cm size Earthen pot/Plastic pot & as per direction of the officer-in-charge.	10.00	Each	172.20	<b>1722.00</b>	INR One Thousand Seven Hundred & Twenty Two Only
55	Providing and displaying of Croton Baby Golden Punctatum Aureum having ht. 23 cm to 30 cm, well developed with fresh and healthy foliage in 15 cm size of Earthen pot/Plastic pot. as per direction of the officer-in-charge.	10.00	Each	30.75	<b>307.50</b>	INR Three Hundred & Seven and Paise Fifty Only
56	Providing and displaying of Raphis palm specimen having ht. 1.50 m to 1.65 m with 40 to 50 lush green suckers, well developed, fresh & healthy foliage leaves in 40 cm size of Earthen Pot/Chali/Tray & as per direction of the officer-in-charge.	20.00	Each	497.15	<b>9943.00</b>	INR Nine Thousand Nine Hundred & Forty Three Only
57	Providing and Displaying Dahlia double kenya variety in different colour well developed with 3 to 4 flowers in half bloom, good foliage stacked with Green painted Bamboo sticks, 45 to 60 cm height in 25 cm Earthen Pot/ Plastic Pot and as per direction of the officer-in-charge.	40.00	Each	76.90	<b>3076.00</b>	INR Three Thousand & Seventy Six Only
58	Providing and Displaying Marigold jaffri orange/yellow/Russet colour well developed with fresh & healthy foliage with 40 to 50 flowers in bloom specimen plant 60 to 75 cm ht in 25 cm Earthen Pot/Plastic Pot and as per direction of the officer-in-charge.	50.00	Each	97.40	<b>4870.00</b>	INR Four Thousand Eight Hundred & Seventy Only
59	Providing and Displaying Cosmos well developed fresh & healthy 20 to 25 cm ht. attractive colors multi branching at blooming stage in 20 cm Earthen Pot/Plastic Pot and as per direction of the officer-in-charge.	30.00	Each	38.95	<b>1168.50</b>	INR One Thousand One Hundred & Sixty Eight and Paise Fifty Only
60	Providing and Displaying Zinnia hybrid double in different colour well developed fresh & healthy 30 to 45 cm ht. (3 to 4 in each pot) full bloom in 25 cm Earthen Pot/Plastic Pot and as per direction of the officer-in-charge.	30.00	Each	41.00	<b>1230.00</b>	INR One Thousand Two Hundred & Thirty Only
61	Carriage of materials by Mechanical Transport including loading, unloading and stacking. Earth upto 5 Km lead.	14.85	cum	224.10	<b>3327.89</b>	INR Three Thousand Three Hundred & Twenty Seven and Paise Eighty Eight Only
62	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer-in-charge. Pre-laminated particle board with decorative lamination on both sides	2.24	sqm	894.00	<b>2002.56</b>	INR Two Thousand & Two and Paise Fifty Six Only
63	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS: 13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required :	1.00	each	4038.80	<b>4038.80</b>	INR Four Thousand & Thirty Eight and Paise Eighty Only

64	Providing and fixing factory made single extruded WPC (Wood Polymer Composite) solid door/window/Clerestory windows & other Frames/ Chowkhat comprising of virgin PVC polymer of K value 58-60 (Suspension Grade), calcium carbonate and natural fibers (wood powder/ rice husk/ wheat husk) and non toxic additives (maximum toxicity index of 12 for 100 gms) fabricated with miter joints after applying PVC solvent cement and screwed with full body threaded star headed SS screws having minimum frame density of 750 kg/cum, screw withdrawal strength of 2200 N (Face) & 1100 N (Edge), minimum compressive strength of 58 N/mm2, modulus of elasticity 900 N/mm2 and resistance to spread of flame of Class A category with property of being termite/borer proof, water/moisture proof and fire retardant and fixed in position with M.S hold fast/lugs/SS dash fasteners of required dia and length complete as per direction of Engineer-In- Charge. (M.S hold fast/lugs or SS dash fasteners shall be paid for separately). Note: For WPC solid door/window frames, minus 5 mm tolerance in dimensions i.e depth and width of profile shall be acceptable. Variation in profile dimensions on plus side shall be acceptable but no extra payment on this account shall be made. Frame size 45 x 70 mm	14.55	meter	560.95	8161.82	INR Eight Thousand One Hundred & Sixty One and Paise Eighty Two Only
65	Providing and fixing factory made single extruded WPC (Wood Polymer Composite) solid plain flush door shutter of required size comprising of virgin polymer of K value 58-60 (Suspension Grade), calcium carbonate and natural fibers (wood powder/ rice husk/wheat husk) and non toxic additives (maximum toxicity index of 12 for 100 gms) having minimum density of 650 kg/cum and screw withdrawal strength of 1800 N (Face) & 900 N (Edge), minimum compressive strength 50 N/mm2, modulus of elasticity 850 N/mm2 and resistance to spread of flame of Class A category with property of being termite/borer proof, water/moisture proof and fire retardant and fixing with stainless steel butt hinges of required size with necessary full body threaded star headed counter sunk S.S screws, all as per direction of Engineer-In- Charge. (Note: stainless steel butt hinges and necessary S.S screws shall be paid separately). 30 mm thick	4.50	sqm	3612.70	16257.15	INR Sixteen Thousand Two Hundred & Fifty Seven and Paise Fifteen Only
66	<b>Total impact of GST for the purpose of CTC</b>	1.000	Nos	0.00	0.00	INR Zero Only
<b>Total in Figures</b>					<b>895513.69</b>	INR Eight Lakh Ninety Five Thousand Five Hundred & Thirteen and Paise Sixty Nine Only
<b>Quoted Rate in Figures</b>			Select		0.00	INR Zero Only
<b>Quoted Rate in Words</b>	<b>INR Zero Only</b>					