

Tender Inviting Authority: Staff officer (E&M), Magadh - Sanghmitra Area, CCL						
Name of the Work / Contract No:	Work of "Power arrangement to operate the Air Conditioning in the canteen and VIP Conference hall during VVIP visit as well as providing and installing LED Lighting fixtures with round down lights in the passage area in front of the VIP canteen at Avantika Transit Camp, as well as replacing damaged lights of the VIP conference hall as needed at Magadh OCP, M-S Area .".				NIT No: G.M.(M-S)/S.O.(E&M)/e-NIT/26-27/14; Dated:- 11.05.2026.	
Category of Services (To Be Selected by Department)			Category of Bidder (To Be Selected by Bidder)			
ITC Not Available	Works Contract		Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :			Select	0.00	0.00	0.00

PRICE SCHEDULE
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Supply of 16 sqmm 4 core Alluminium Un Armoured cable 1.1 Kv grade ISI marked.	250.00	Mtr		0.00	INR Zero Only
2	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on wall surface as required.Upto 35 sq. mm (clamped with 1mm thick saddle)	250.00	Mtr		0.00	INR Zero Only
3	Wiring for circuit/ submain wiring alongwith earth wire with the 2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire wire sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required.	40	mtr		0.00	INR Zero Only
4	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with piano type switch, phenolic laminated sheet, suitable size M.S. box and earthing the point with 1.5 sq.mm.FRLS PVC insulated copper conductor single core cable etc. as required.Group A	8	point		0.00	INR Zero Only
5	Supplying and fixing following rating, double pole , (single phase and neutral), 240 volts, residual current circuit breaker (RCCB), having a sensitivity current 30 mA in the existing MCB DB complete with connections, testing and commissioning etc.as required. 25A	2	No.		0.00	INR Zero Only
6	Supplying and drawing following sizes of FRLS PVC insulated copper conductor single core cable in the existing surface/ recessed steel/ PVC conduit as required. 2x 6 sq.mm	20	Mtr		0.00	INR Zero Only
7	Supplying and fixing 5 amps to 32 amps rating, 240/ 415volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc as required. Single pole & neutral	6	No.		0.00	INR Zero Only
8	Supplying and fixing Cable End Box (Loose Wire Box) suitable for following single pole and neutral, sheet steel, MCB distribution board, 240 Volts, on surface/ recess, complete with testing and commissioning etc. as required.For 6 way, Double door SPN MCBDB	1	No.		0.00	INR Zero Only
9	Provision of Surface Mounting LED Surface ceiling Luminaries fittings 20watt Fixture / Luminaire should be die-cast aluminum /CRCA/Extruded aluminum	23	Nos		0.00	INR Zero Only
10	Recess-mounting low-height round LED 24 watt downlighter designed with excellent thermally managed aluminium pressure die-cast housing with heat-dissipating fins for larger surface area 1x1	7	Nos		0.00	INR Zero Only
11	Installation, testing and commissioning of pre-wired, fluorescent fitting/ compact fluorescent fitting of all types, complete with all accessories and tube/lamp etc. directly on ceiling/ wall, including connections with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable and earthing etc. as required.	30	Nos		0.00	INR Zero Only
12	Supplying and fixing of following ways surface/ recess mounting, vertical type, 415 V, TPN MOB distribution board of sheet steel, dust protected, duly powder painted, inclusive of 200 A tinned copper bus bar, common neutral link, earth bar, din bar for mounting MCBs (but without MCBs and incomer) as required.(Note : Vertical type MOB TPDB is normally used where 3 phase outlets are required.)4 way (4 + 12), Double door.	1	Nos		0.00	INR Zero Only
13	Providing and fixing 100 A,30KA,FP MCCB rating and breaking capacity and 4 pole MCCB with thermomagnetic release and terminal spreaders in existing cubicle panel board including drilling holes in cubicle panel, making connections, etc. as required.	2	Each		0.00	INR Zero Only
14	Providing of Onload Manual switch disconnecter changer with sheet steel enclosure Type, 100 Amp	1	Each		0.00	INR Zero Only
15	Providing of Onload Manual switch disconnecter changer with sheet steel enclosure Type, 250 Amp for changing of damaged changeover switch previously installed	1	Each		0.00	INR Zero Only
16	Installation charge of onload changeover switch in metal fabricated stand with connection	2	JOB		0.00	INR Zero Only
17	Total impact of GST for the purpose of CTC	1.000	Job	0.00	0.00	INR Zero Only
Total in Figures					0.00	0.00 INR Zero Only
Quoted Rate in Words						INR Zero Only