

Tender Inviting Authority: Staff officer (E&M), Amrapali- Chandragupta Area, CCL					
Name of the Work / Contract No:	Electrical Rewiring and facade decoration lighting in outer structure for aesthetic beautification of community centre at Amrapali OCP, A-C Area			NIT No: G.M.(A-C)/S.O.(E&M)/e-NIT/26-27/05 ; Dated: 12.05.2026	
.	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)			
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be updated after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	6	7	8
1	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with piano type switch, phenolic laminated sheet, suitable size M.S. box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc. as required. Group A	38.000	Nos.		0.00	INR Zero Only
2	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required. 2 X 6 sq. mm + 1 X 6 sq. mm earth wire	80.000	Mtr.		0.00	INR Zero Only
3	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required.2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	100.00	Mtr.		0.00	INR Zero Only
4	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required. 2 X 1.5 sq. mm + 1 X 1.5 sq. mm earth wire	210.00	Mtr.		0.00	INR Zero Only

5	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator). 6 way , Double door	1.00	Nos.		0.00	INR Zero Only
6	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Double pole	6.00	Nos.		0.00	INR Zero Only
7	Providing of surface mount LED panel light 12 watt	16.00	Nos.		0.00	INR Zero Only
8	Providing of LED Rope light/ Strip light weatherproof, IP65, 50M	4.00	Nos.		0.00	INR Zero Only
9	Providing of LED 12 watt façade light/ spike light, weatherproof IP 65	12.00	Nos.		0.00	INR Zero Only
10	Providing of wall washer 7W 3000K Liner LED light with remote control, waterproof IP65	8.00	Nos.		0.00	INR Zero Only
11	Providing of LED Up down wall highlighter 12W, 3000K	12.00	Nos.		0.00	INR Zero Only
12	Providing of Air circulator type Electric Fan	6.00	Nos.		0.00	INR Zero Only
13	Erection/ Contractor profit of item No. 7 to 12 @ 15%	1.00	Job		0.00	INR Zero Only
14	Total impact of GST for the purpose of CTC	1.000	Job	0.00	0.00	INR Zero Only
Total in Figures					0.00	INR Zero Only
Quoted Rate in Words						INR Zero Only