

Validate

Print

Help

Tender Inviting Authority: Staff Officer(Civil), NK Area.

Name of Work:-Provision of D.I Pipeline form Filter Plant (IWSS Dakra) to Subash Nagar Colony ,Officers Colony and Mohan Nagar including the raw water pipeline form KDH Settling Pond to Filter Plant ,Dakra under GM Unit,NK Area.

	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department		
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	(PART -A From IWSS Dakra to Subash Nagar colony ,Officers Colony & Mohan Nagar colony) Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.All kinds of soil.	1947.60	Cum	205.80	400816.08	INR Four Lakh Eight Hundred & Sixteen and Paise Eight Only
2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer-in-charge.Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix).	11.75	Cum	1464.60	17209.05	INR Seventeen Thousand Two Hundred & Nine and Paise Five Only
3	Dismantling manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge :bituminous road.	7.20	Sqm	259.50	1868.40	INR One Thousand Eight Hundred & Sixty Eight and Paise Forty Only
4	Providing and laying S&S Centrifugally Cast (Spun) / Ductile Iron Pipes conforming to IS : 8329 :250 mm dia Ductile Iron Class K-9 pipes.	3900.00	Meter	2552.75	9955725.00	INR Ninety Nine Lakh Fifty Five Thousand Seven Hundred & Twenty Five Only
5	Providing and laying S&S Centrifugally Cast (Spun) / Ductile Iron Pipes conforming to IS : 8329 :200 mm dia Ductile Iron Class K-9 pipes.	410.00	Meter	2951.25	1210012.50	INR Twelve Lakh Ten Thousand & Twelve and Paise Fifty Only
6	Providing push-on-joints to Centrifugally (Spun) Cast Iron Pipes or Ductile Iron Pipes including testing of joints and the cost of rubber gasket ,250 mm dia pipes.	710.00	Each	229.65	163051.50	INR One Lakh Sixty Three Thousand & Fifty One and Paise Fifty Only
7	Providing push-on-joints to Centrifugally (Spun) Cast Iron Pipes or Ductile Iron Pipes including testing of joints and the cost of rubber gasket ,200 mm dia pipes.	75.00	Each	188.10	14107.50	INR Fourteen Thousand One Hundred & Seven and Paise Fifty Only
8	Providing and laying S&S C.I. Standard specials such as tees, bends, collars tapers and caps etc, suitable for flanged jointing as per IS : 1538 :Up to 300 mm dia.	40.00	Quintal	6,466.10	258644.00	INR Two Lakh Fifty Eight Thousand Six Hundred & Forty Four Only
9	Providing and laying S&S C.I. Standard specials suitable for mechanical jointing as per IS : 13382 :Up to 300 mm dia.	10.00	Quintal	9944.80	99448.00	INR Ninety Nine Thousand Four Hundred & Forty Eight Only

10	Providing and fixing C.I. sluice valves (with cap) complete with bolts, nuts, rubber insertions etc. (the tail pieces if required will be paid separately) :250 mm diameter. Class II.	3.00	Each	26102.15	78306.45	INR Seventy Eight Thousand Three Hundred & Six and Paise Forty Five Only
11	Providing and fixing C.I. sluice valves (with cap) complete with bolts, nuts, rubber insertions etc. (the tail pieces if required will be paid separately) :200 mm diameter. Class II.	3.00	Each	16137.10	48411.30	INR Forty Eight Thousand Four Hundred & Eleven and Paise Thirty Only
12	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	10.92	Cum	1438.10	15704.05	INR Fifteen Thousand Seven Hundred & Four and Paise Five Only
13	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources) .	5.19	Cum	6,072.40	31515.76	INR Thirty One Thousand Five Hundred & Fifteen and Paise Seventy Six Only
14	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 Cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources) .	1.08	Cum	7,424.45	8018.41	INR Eight Thousand & Eighteen and Paise Forty One Only
15	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 5 in foundation and plinth in:Cement mortar 1:4 (1 cement : 4 coarse sand).	22.68	Cum	6770.05	153544.73	INR One Lakh Fifty Three Thousand Five Hundred & Forty Four and Paise Seventy Three Only
16	12 mm cement plaster of mix :1:4 (1 cement: 4 fine sand).	82.60	Sqm	245.90	20311.34	INR Twenty Thousand Three Hundred & Eleven and Paise Thirty Four Only
17	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and for all lift	1701.77	Cum	118.65	201915.01	INR Two Lakh One Thousand Nine Hundred & Fifteen and Paise One Only
18	CARRIAGE OF MATERIALS By Mechanical Transport including loading,unloading and stacking Lime, moorum, building rubbish Lead - 5 km.	12.32	Cum	179.25	2208.36	INR Two Thousand Two Hundred & Eight and Paise Thirty Six Only
19	CARRIAGE OF MATERIALS By Mechanical Transport including loading,unloading and stacking Earth Lead - 5 km.	245.83	Cum	224.10	55090.50	INR Fifty Five Thousand & Ninety and Paise Fifty Only
20	(PART-B Row water arrangement from KDH settling Pond) Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.All kinds of soil.	697.50	Cum	205.80	143545.50	INR One Lakh Forty Three Thousand Five Hundred & Forty Five and Paise Fifty Only
21	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix).	5.40	Cum	1464.60	7908.84	INR Seven Thousand Nine Hundred & Eight and Paise Eighty Four Only
22	Providing and laying S&S Centrifugally Cast (Spun) / Ductile Iron Pipes conforming to IS : 8329 :250 mm dia Ductile Iron Class K-9 pipes.	1550.00	Meter	2552.75	3956762.50	INR Thirty Nine Lakh Fifty Six Thousand Seven Hundred & Sixty Two and Paise Fifty Only
23	Providing push-on-joints to Centrifugally (Spun) Cast Iron Pipes or Ductile Iron Pipes including testing of joints and the cost of rubber gasket ,250 mm dia pipes.	282.00	Each	229.65	64761.30	INR Sixty Four Thousand Seven Hundred & Sixty One and Paise Thirty Only
24	Providing and laying S&S C.I. Standard specials such as tees, bends, collars tapers and caps etc, suitable for flanged jointing as per IS : 1538 :Up to 300 mm dia.	20.00	Quantal	6,466.10	129322.00	INR One Lakh Twenty Nine Thousand Three Hundred & Twenty Two Only
25	Providing and laying S&S C.I. Standard specials suitable for mechanical jointing as per IS : 13382 :Up to 300 mm dia.	10.00	Quantal	9,944.80	99448.00	INR Ninety Nine Thousand Four Hundred & Forty Eight Only
26	Providing and fixing C.I. sluice valves (with cap) complete with bolts, nuts, rubber insertions etc. (the tail pieces if required will be paid separately) :250 mm diameter. Class II.	1.00	Each	26102.15	26102.15	INR Twenty Six Thousand One Hundred & Two and Paise Fifteen Only

27	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources) .	0.60	Cum	6,072.40	3643.44	INR Three Thousand Six Hundred & Forty Three and Paise Forty Four Only
28	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 Cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources) .	1.20	Cum	7424.45	8909.34	INR Eight Thousand Nine Hundred & Nine and Paise Thirty Four Only
29	Filling available excavated earth (excluding rock) in trenches, plinth. sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and for all lift	606.12	Cum	118.65	71916.14	INR Seventy One Thousand Nine Hundred & Sixteen and Paise Fourteen Only
30	PART-C Distribution pipeline) Providing, laying and fixing following dia G.I. pipe (medium class) in ground complete with G.I. fittings including trenching (75 cm deep)and re-filling etc as required 150mm dia.	1275.00	Meter	2386.00	3042150.00	INR Thirty Lakh Forty Two Thousand One Hundred & Fifty Only
31	Providing, laying and fixing following dia G.I. pipe (medium class) in ground complete with G.I. fittings including trenching (75 cm deep)and re-filling etc as required 100mm dia.	2180.00	Meter	1579.00	3442220.00	INR Thirty Four Lakh Forty Two Thousand Two Hundred & Twenty Only
32	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. External work. 50 mm dia nominal bore.	300.00	Meter	710.45	213135.00	INR Two Lakh Thirteen Thousand One Hundred & Thirty Five Only
33	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. External work. 25 mm dia nominal bore.	600.00	Meter	418.80	251280.00	INR Two Lakh Fifty One Thousand Two Hundred & Eighty Only
34	Making connection of G.I. distribution branch with Cl. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete:50 to 80 mm nominal bore.	10.00	Each	1,063.85	10638.50	INR Ten Thousand Six Hundred & Thirty Eight and Paise Fifty Only
35	Making connection of G.I. distribution branch with Cl. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete:25 to 40 mm nominal bore	40.00	Each	592.15	23686.00	INR Twenty Three Thousand Six Hundred & Eighty Six Only
36	Providing and fixing C.I. sluice valves (with cap) complete with bolts, nuts, rubber insertions etc. (the tail pieces if required will be paid separately) :150 mm diameter.Class II	8.00	Each	7642.25	61138.00	INR Sixty One Thousand One Hundred & Thirty Eight Only
37	Providing and fixing C.I. sluice valves (with cap) complete with bolts, nuts, rubber insertions etc. (the tail pieces if required will be paid separately) :100 mm diameter.Class II	14.00	Each	5,221.60	73102.40	INR Seventy Three Thousand One Hundred & Two and Paise Forty Only
38	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) :50 mm nominal bore	5.00	Each	772.05	3860.25	INR Three Thousand Eight Hundred & Sixty and Paise Twenty Five Only
39	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) :25 mm nominal bore	40.00	Each	440.50	17620.00	INR Seventeen Thousand Six Hundred & Twenty Only
40	Dismantling manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge :bituminous road.	19.00	Sqm	259.50	4930.50	INR Four Thousand Nine Hundred & Thirty and Paise Fifty Only
41	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.All kinds of soil.	19.60	Cum	205.80	4034.09	INR Four Thousand & Thirty Four and Paise Nine Only
42	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources) .	5.57	Cum	6,072.40	33823.27	INR Thirty Three Thousand Eight Hundred & Twenty Three and Paise Twenty Seven Only

43	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:Cement mortar 1:6 (1 cement : 6 coarse sand).	18.93	Cum	6770.05	128157.05	INR One Lakh Twenty Eight Thousand One Hundred & Fifty Seven and Paise Five Only
44	12 mm cement plaster finished with a floating coat of neat cement of mix :1:4 (1 cement: 4 fine sand).	91.53	Sqm	303.20	27751.90	INR Twenty Seven Thousand Seven Hundred & Fifty One and Paise Ninety Only
45	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources).	10.80	Cum	7424.45	80184.06	INR Eighty Thousand One Hundred & Eighty Four and Paise Six Only
46	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					24665938.16	INR Two Crore Forty Six Lakh Sixty Five Thousand Nine Hundred & Thirty Eight and Paise Sixteen Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only					