

Percentage BoQ

Tender Inviting Authority: Staff Officer (Civil),CCL, Dhori Area

Name of Work: - AMC for main pipeline for water distribution of NSD Colony , Singh Nagar colony, Dhori Khas colony and remaining areas under Dhori khas UG project , Dhori Area (for 2 years)

	Category of Services (To Be Selected by Department)	Category of Bidder(To Be Selected by Bidder)	To Be Entered by Department		
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT in Words
1	2	3	4	5	6	7
1	Laying of G.I. pipes complete with G.I. fittings including trenching and refilling etc. (external work):Above 40mm upto 150mm	1530.00	metre	₹150.16	229745.84	INR Two Lakh Twenty Nine Thousand Seven Hundred & Forty Five and Paise Eighty Four Only
2	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc:External work:80 mm dia nominal bore	180.00	metre	₹1,117.95	201231.00	INR Two Lakh One Thousand Two Hundred & Thirty One Only
3	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc:External work:100 mm dia nominal bore	240.00	metre	₹1,579.00	378960.00	INR Three Lakh Seventy Eight Thousand Nine Hundred & Sixty Only
4	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc:External work:150 mm dia nominal bore	90.00	metre	₹2,386.00	214740.00	INR Two Lakh Fourteen Thousand Seven Hundred & Forty Only
5	Dism antling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes manually / by machanical means including stacking of pipes within 50 metres lead as per direction of Engineer-in-charge :above 40mm	1530.00	metre	₹102.45	156748.50	INR One Lakh Fifty Six Thousand Seven Hundred & Forty Eight and Paise Fifty Only
6	Providing and fixing bolts including nuts and washers complete.	100.00	kg	₹109.60	10960.00	INR Ten Thousand Nine Hundred & Sixty Only
7	Providing and fixing 3" GI Flanges	40.00	each	₹268.31	10732.40	INR Ten Thousand Seven Hundred & Thirty Two and Paise Forty Only
8	Providing and fixing 4 "GI Flanges	40.00	each	₹383.30	15332.00	INR Fifteen Thousand Three Hundred & Thirty Two Only
9	Providing and fixing 6 "GI Flanges	40.00	each	₹574.94	22997.60	INR Twenty Two Thousand Nine Hundred & Ninety Seven and Paise Sixty Only
10	Providing and fixing gun metal gate valve with C.I. wheel of approved quality(screwed end) :80 mm nominal bore.	20.00	each	₹2,141.95	42839.00	INR Forty Two Thousand Eight Hundred & Thirty Nine Only
11	Providing and fixing C.I. sluice valves (with cap) complete with bolts, nuts, rubber insertions etc. (the tail pieces if required will be paid separately) : 100 mm diameter:Class II.	15.00	each	₹5,221.60	78324.00	INR Seventy Eight Thousand Three Hundred & Twenty Four Only
12	Providing and fixing C.I. sluice valves (with cap) complete with bolts, nuts, rubber insertions etc. (the tail pieces if required will be paid separately) : 125 mm diameter: Class II.	5.00	each	₹6,087.40	30437.00	INR Thirty Thousand Four Hundred & Thirty Seven Only

13	Providing and fixing C.I. sluice valves (with cap) complete with bolts, nuts, rubber insertions etc. (the tail pieces if required will be paid separately) :150 mm diameter:Class II.	8.00	each	₹7,642.25	61138.00	INR Sixty One Thousand One Hundred & Thirty Eight Only
14	Welding by gas or electric plant including transportation of plant at site etc. complete.	40000.00	cm	₹3.60	144000.00	INR One Lakh Forty Four Thousand Only
15	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30cm in depth. 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m, disposed earth to be levelled and neatly dressed.all kinds of soil	270.00	cum	₹139.70	37719.00	INR Thirty Seven Thousand Seven Hundred & Nineten Only
16	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m	270.00	cum	₹118.65	32035.50	INR Thirty Two Thousand &Thirty Five and Paise Fifty Only
17	Brick work with common burnt clay FPS (non modular) bricks of class designation 5 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)	6.48	cum	₹6,770.05	43869.92	INR Forty Three Thousand Eight Hundred & Sixty Nine and Paise Ninety Two Only
18	12 mm cement plaster of mix :1:6 (1 cement: 6 fine sand)	43.20	sqm	₹230.60	9961.92	INR Nine Thousand Nine Hundred & Sixty One and Paise Ninety Two Only
19	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 .mm nominal size).	5.00	cum	₹7,424.45	37122.25	INR Thirty Seven Thousand One Hundred & Twenty Two and Paise Twenty Five Only
20	Dismantling sluice Valve for taking out check nut , spindles and refix it after getting repaired :50mm	5.00	each	₹2,125.80	10629.00	INR Ten Thousand Six Hundred & Twenty Nine Only
21	Dismantling sluice Valve for taking out check nut , spindles and refix it after getting repaired :80mm	30.00	each	₹2,358.10	70743.00	INR Seventy Thousand Seven Hundred & Forty Three Only
22	Dismantling sluice Valve for taking out check nut , spindles and refix it after getting repaired :100mm	24.00	each	₹2,706.55	64957.20	INR Sixty Four Thousand Nine Hundred & Fifty Seven and Paise Twenty Only
23	Dismantling sluice Valve for taking out check nut , spindles and refix it after getting repaired :150mm	12.00	each	₹3,171.15	38053.80	INR Thirty Eight Thousand &Fifty Three and Paise Eighty Only
24	Clearing jungle including uprooting of rank vegetation, grass, brush,wood, trees and saplings of girth upto 30 cm measured at a height of 1m above ground level and removal of rubbish upto a distance of 50 m outside the periphery of the area cleared	4900.00	sqm	₹10.55	51695.00	INR Fifty One Thousand Six Hundred & Ninety Five Only
25	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					1994971.93	INR Nineteen Lakh Ninety Four Thousand Nine Hundred & Seventy One and Paise Ninety Three Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only					