

Item Rate BoQ

Tender Inviting Authority: GM (Excv) /STAFF OFFICER (Excv), Rajrappa Area

Name of the Work / Contract No:	Repairing and reconditioning of Field Switch- 01 No. Make ELEC-TROTEKNICA, 6.6 KV, 400Amp,sl.no-SP/O/995, of WK-12C TZ EXC-2990 (Garur) Electric Rope Shovel of Rajrappa Project.			NIT No: GM(R)/Excv/Tender-NIT/26-27/02 Date 11/05/2026		
	Category of Services (To Be Selected by Department)	Category of Bidder (To Be Selected by Bidder)	To Be Entered by Department			
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	0.00
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1	(A) Mechanical Components Complete repairing/oberhauling of ON-OFF/spring charge Mechanism	1.000	No.			0.00	INR Zero Only
2	Denting and painting of complete field switch body including door hinges/lock nut bolts and naming/numbering on field switch.	1.000	No.			0.00	INR Zero Only
3	(B) Electrical Components Vacuum Interrupter 6.6KV, 13.1KA, Type-WL34599M3+ make-Crompton Greaves.	1.000	No.			0.00	INR Zero Only
4	Digital Earth relay leakage (Make-Prok Dv's) with cast resin CBCT (150mm)	1.000	No.			0.00	INR Zero Only
5	Digital over current, short circuit, Earth fault protection relay model-IRI-Pro 3I-EI, Make- C&S	1.000	No.			0.00	INR Zero Only
6	OV/UV protection relay make-minilec, model-HLV D2	1.000	No.			0.00	INR Zero Only
7	OL protection relay make-minilec, model- MPR D2	1.000	No.			0.00	INR Zero Only
8	Digital Ampere meter display system: CTR 100-200/5A, make-L&T, Model-VEGA	1.000	No.			0.00	INR Zero Only
9	Digital Voltmeter Display system : 6.6KV/110V, Make-L&T, Model-VEGA	1.000	No.			0.00	INR Zero Only
10	ON & OFF DC Coil	2.000	Nos.			0.00	INR Zero Only
11	repairing of Isolator/Load Break switch assembly, Type-NSSC/ET, 630Amp	1.000	No.			0.00	INR Zero Only
12	Ampere Selector Switch	1.000	No.			0.00	INR Zero Only
13	Voltage Selector Switch	1.000	No.			0.00	INR Zero Only

14	Rotary switch 3-pole 4NO/4NC inside breaker Mechanism	1.000	No.			0.00	INR Zero Only
15	Push switch for ON/OFF/Test/Reset Circuit with aux NO/NC	4.000	Nos.			0.00	INR Zero Only
16	Push switch lock type Emergency circuit with NO/NC	1.000	No.			0.00	INR Zero Only
17	Complete Indication lamp set 110V/0.5W for tripping (Red/yellow/blue/amber/white/green	6.000	No.			0.00	INR Zero Only
18	Wiring, lugs and other accessories	1.000	No.			0.00	INR Zero Only
19	(C)Labour Cost Highly skilled electrician 1 no. X 7 shift	7.000	Nos.			0.00	INR Zero Only
20	Electrician Helper 02 no. X 7 shift	14.000	Nos.			0.00	INR Zero Only
21	Total impact of GST for the purpose of CTC	1.000	No.		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					