

Item Rate BoQ

Tender Inviting Authority: Project Engineer(E&M), Bhurkunda Colliery, Barka-Sayal Area, CCL.						
Name of the Work / Contract No:	Installation and commissioning of rear door interlocking of 3.3KV or 11KV VCB-OCB and maintenance free chemical earth pit for transformer neutral earth and body earth and OCB VCB earth of main 11KV/3.3KV substation under Bhurkunda Colliery.			NIT No. : PE(EnM)/BHK/e Tender/26-27/05 Dated: 14.05.2026		
Category of Services (To Be Selected by Department)			Category of Bidder (To Be Selected)			
ITC Available	Works Contract		Bidder's Status (Mandatory)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :			Select	0.00	0.00	0.00

PRICE SCHEDULE
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	TEXT #	NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Item Code / Make	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	3	4	12	6	7	8
1	A. Rear door interlocking VCB-OCB and Painting Providing and fixing of Limit Switch	1	39	Nos.	INR		0.00	INR Zero Only
2	Providing and fixing of support Base plate for limit switch and accessories.	2	39	Mtrs.	INR		0.00	INR Zero Only
3	Providing and fixing of Nut & Bolt	3	18	KG	INR		0.00	INR Zero Only
4	Providing and fixing of material for wiring with ferrul lug and tie belt	4	16	Nos.	INR		0.00	INR Zero Only
5	Material for painting of VCB and OCB	5	16	Nos.	INR		0.00	INR Zero Only
6	B. Maintenance free chemical earth pit for transformer neutral earth and body earth and OCB VCB earth Providing and fixing of support insulator	6	115	Nos.	INR		0.00	INR Zero Only
7	With 3 mtrs GI pipes having outer pipe dia of 50mm having 80-200 micron galvanising inner pipe dia of 25mm having 200-259 micron galvanizing, connection terminal dia of 12mm in nominal soil with 50 KG (two bag) back filling bentonite compound UL listed and conform to relevant international / indian standard around electrode upto ground level.	7	10	Nos.	INR		0.00	INR Zero Only
8	Providing and fixing GI. tape 20 mm X 3 mm thick on parapet or surface of wall for lightning conductor complete as required.(For vertical run)	8	390	Mtrs.	INR		0.00	INR Zero Only
9	Excavation of the cable trenches in hard rock not exceeding 1.5 metres in width, and lift upto 1.5 metres, including getting out the excavated soil and disposal of excavated soil as directed within a lead of 50 metres.	9	40	Cum	INR		0.00	INR Zero Only
10	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	10	20	Cum	INR		0.00	INR Zero Only
11	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6(1 cement: 6 coarse sand)	11	10	Cum	INR		0.00	INR Zero Only
12	Total impact of GST for the purpose of CTC	12	1.000	Nos	INR	0.00	0.00	INR Zero Only
Total in Figures							0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only							