

Validate

Print

Help

Percentage BoQ

Tender Inviting Authority: Staff Officer (Civil), Barka-Sayal Area

Name of Work: Avenue plantation along village roads adjacent to project boundary under DRP and NCRAP under Bhurkunda project, Barka-Sayal area

	Category of Services (To Be Selected by Department)	Category of Bidder(To Be Selected by Bidder)	To Be Entered by Department		
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT in Words
1	2	3.00	4	5	6	7
1	Item Description/ Heading					
1.01	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	388.8	Cum	188.45	73269.36	INR Seventy Three Thousand Two Hundred & Sixty Nine and Paise Thirty Six Only
1.02	Supply of cow dung.	194.4	Cum	300.00	58320.00	INR Fifty Eight Thousand Three Hundred & Twenty Only
1.03	Supplying & stacking at site: Good Earth.	194.4	Cum	493.05	95848.92	INR Ninety Five Thousand Eight Hundred & Forty Eight and Paise Ninety Two Only
1.04	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	388.8	Cum	114.40	44478.72	INR Forty Four Thousand Four Hundred & Seventy Eight and Paise Seventy Two Only
1.05	Providing and stacking of Azadirachta indica (Neem) of height 120-130cm in big polybag of size 25 cm as per direction of the officer-in-charge.	600	Nos	65.00	39000.00	INR Thirty Nine Thousand Only

1.06	Providing and stacking of Cassia fistula (Amaltash) of height 120-135 cm. in big poly bags of size 25 cm as per direction of the officer-in-charge.	600	Nos	65.00	39000.00	INR Thirty Nine Thousand Only
1.07	Providing and stacking of Pongamia glabra (Papri/karanj) of height 120-135 cm. in big poly bag of size 25 cm as per direction of the officer-in-charge.	600	Nos	50.00	30000.00	INR Thirty Thousand Only
1.08	Fencing with R.C.C. post placed at required distance, embedded in cement concrete blocks, every 15th post, last but one end post and corner post shall be strutted on both sides and end post one side only, provided with horizontal lines and two diagonals of barbed wire weighing 9.38 kg per 100 metres (minimum), between the two posts fitted and fixed with G.I. staples on wooden plugs or G.I. binding wire tied to 6 mm bar nibs fixed while casting the post (cost of R.C.C. posts, struts, earth work and concrete to be paid for separately) :- Payment to be made per metre cost of total length of barbed wire used. 16.17.1 With G.I. barbed wire	51840	mtr	10.25	531360.00	INR Five Lakh Thirty One Thousand Three Hundred & Sixty Only
1.09	Safeda ballies 125 mm dia.	8640	mtr	40.00	345600.00	INR Three Lakh Forty Five Thousand Six Hundred Only
1.10	Maintenance of plant. (2 labour per day)	1460	days	628.37	917420.20	INR Nine Lakh Seventeen Thousand Four Hundred & Twenty and Paise Twenty Only
1.11	Total impact of GST for the purpose of CTC	1.00	Nos	0.00	0.00	INR Zero Only
Total in Figures					2174297.20	INR Twenty One Lakh Seventy Four Thousand Two Hundred & Ninety Seven and Paise Twenty Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words	INR Zero Only					