

Validate

Print

Help

Percentage BoQ

Tender Inviting Authority: PE(Civil), AKKOCP, B&K Area

Name of Work: Installation of pillars around Forest Boundary for demarcation purpose at Konar Exp. OCP of BnK Area.

	Category of Services (To Be Selected by Department)	Category of Bidder(To Be Selected by Bidder)	To Be Entered by Department		
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	23.760	CUM	205.80	4889.81	INR Four Thousand Eight Hundred & Eighty Nine and Paise Eighty One Only
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	28.960	CUM	7424.45	215012.07	INR Two Lakh Fifteen Thousand & Twelve and Paise Seven Only
3	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	933.240	Kg	105.60	98550.14	INR Ninety Eight Thousand Five Hundred & Fifty and Paise Fourteen Only
4	Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc. for mass concrete.	74.250	CUM	277.90	20634.08	INR Twenty Thousand Six Hundred & Thirty Four and Paise Seven Only
5	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	138.600	SQM	112.30	15564.78	INR Fifteen Thousand Five Hundred & Sixty Four and Paise Seventy Eight Only
6	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					354650.88	INR Three Lakh Fifty Four Thousand Six Hundred & Fifty and Paise Eighty Eight Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words						INR Zero Only