

Validate

Print

Help

Percentage BoQ

Tender Inviting Authority: Staff Officer(Civil), Kuju Area

Name of Work : Provision of RCC guard wall with PCC approach road and speed breaker near RFID checkpoint under Karma OCP of Kuju Area.

	Category of Services (To Be Selected by Department)	Category of Bidder(To Be Selected by Bidder)	To Be Entered by Department		
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
0	Item Description/ Heading					
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.Ordinary rock.	45.93	CUM	392.85	18041.64	INR Eighteen Thousand &Forty One and Paise Sixty Four Only
2	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tipper to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer- in-Charge. With material conforming to Grade-II (size range 53 mm to 0.075 mm) having CBR Value-25	25.00	CUM	2451.45	61286.25	INR Sixty One Thousand Two Hundred & Eighty Six and Paise Twenty Five Only
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:1.5:3 (1 Cement: 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	37.50	CUM	7907.55	296533.13	INR Two Lakh Ninety Six Thousand Five Hundred & Thirty Three and Paise Twelve Only
4	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	25.00	CUM	1438.10	35952.50	INR Thirty Five Thousand Nine Hundred & Fifty Two and Paise Fifty Only

5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	2.03	CUM	7424.45	15034.51	INR Fifteen Thousand &Thirty Four and Paise Fifty One Only
6	Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc. for mass concrete.	54.00	Sqm	277.90	15006.60	INR Fifteen Thousand &Six and Paise Sixty Only
7	Centering and shuttering including strutting, propping etc. and removal of form for Walls (any thickness) including attached pilasters, butteresses, plinth and string courses etc.	60.40	Sqm	562.75	33990.10	INR Thirty Three Thousand Nine Hundred & Ninety and Paise Ten Only
8	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	57.60	CUM	8343.45	480582.72	INR Four Lakh Eighty Thousand Five Hundred & Eighty Two and Paise Seventy Two Only
9	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.Thermo-Mechanically Treated bars of grade Fe-500D or more.	4608.00	Kg	105.60	486604.80	INR Four Lakh Eighty Six Thousand Six Hundred & Four and Paise Eighty Only
10	Providing and fixing of Heavy Duty Rubber Speed Breakers as per direction of EIC.	20.00	Mtr	1800.00	36000.00	INR Thirty Six Thousand Only
11	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work.	55.20	Sqm	112.30	6198.96	INR Six Thousand One Hundred & Ninety Eight and Paise Ninety Six Only
12	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					1485231.20	INR Fourteen Lakh Eighty Five Thousand Two Hundred & Thirty One and Paise Twenty Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				