

Validate

Print

Help

**Item Rate BoQ**

Tender Inviting Authority: <b>Manager(EnM), Central Hospital, Ramgarh</b>						
Name of the Work / Contract No:	Complete Concealed rewiring of Emergency building of Central Hospital, Ramgarh.			CCL/CHR/E&M//e-Tender/2026-27/01		
	<b>Category of Services (To Be Selected by Department)</b>	<b>Category of Bidder (To Be Selected by Bidder)</b>	<b>To Be Entered by Department</b>			
<b>ITC Not Available</b>	<b>Works Contract</b>	<b>Bidder's Status (Mandatory)</b>		<b>Total GST(in Rs.)</b>	<b>GST to be Paid By Bidder (in Rs.)</b>	<b>GST to be Paid By CIL/Subsidiary (in Rs.)</b>
Name of the Bidder/ Bidding Firm / Company :		<b>Select</b>	<b>18</b>	<b>0.00</b>	<b>0.00</b>	<b>0.00</b>

**PRICE SCHEDULE**

**(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )**

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate (Without Taxes) in Rs. P	BASIC RATE (Without Taxes) In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
1.01	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required. Group C.	886.00	Points			<b>0.00</b>	INR Zero Only
1.02	Supplying and fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connection but excluding modular plate etc. as required .	185.00	Nos			<b>0.00</b>	INR Zero Only
1.03	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 3 pin 5/6 A modular socket outlet and 5/6 A modular switch, connections etc. as required.	469.00	Nos			<b>0.00</b>	INR Zero Only
1.04	Supplying and fixing suitable size GI box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 5/6 & 15/16 A modular socket outlet and 15/16 A modular switch, connections etc. as required.	299.00	Nos			<b>0.00</b>	INR Zero Only
1.05	Wiring for circuit/sub main wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor single core cable in surface/recessed PVC conduit as required. 2x2.5 sq.mm +1x2.5 sq. mm earth wire.	1515.00	Mtrs			<b>0.00</b>	INR Zero Only
1.06	Wiring for circuit/sub main wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor single core cable in surface/recessed PVC conduit as required. 2x4 sq.mm +1x 4 sq. mm earth wire.	2260.00	Mtrs			<b>0.00</b>	INR Zero Only

1.07	Wiring for circuit/sub main wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor single core cable in surface/recessed PVC conduit as required. 2x6 sq.mm +1x 6 sq. mm earth wire	475.00	Mtrs			0.00	INR Zero Only
1.08	Wiring for circuit/sub main wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor single core cable in surface/recessed PVC conduit as required. 4 x10 sq.mm +2x 6 sq. mm earth wire	160.00	Mtrs			0.00	INR Zero Only
1.09	Supplying and fixing 5 Amps to 32 Amps rate 240 V 'C' series MCB suitable for inductive load of following poles in the existing MCB DB complete with connections testing and commissioning etc as required. Single Pole.	432.00	Nos			0.00	INR Zero Only
1.1	Supplying and fixing 5 Amps to 32 Amps rate 240 V 'C' series MCB suitable for inductive load of following poles in the existing MCB DB complete with connections testing and commissioning etc as required. Double Pole.	40.00	Nos			0.00	INR Zero Only
1.11	Supplying and fixing following rating , double pole ( single phase and neutral ) 240V residual current circuit breaker (RCCB) , having a sensitivity current up to 300 millanmperes , in the existing MCB DB complete with connections, testing and commissioning , earthing etc as required. 63 amps.	24.00	Nos			0.00	INR Zero Only
1.12	Supplying and fixing following way, horizontal type three pole and neutral, sheet steel, MOB distribution board, 415 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/isolator) 6 way (4 +18) Double door.	24.00	Nos			0.00	INR Zero Only
1.13	Supplying and fixing 20 A, 240 V, SPN Industrial type socket outlet, with 2 pole and earth, metal enclosed plug top along with 20 A "C" curve, SP, MCB, in sheet steel enclosure, on surface or in recess, with chained metal cover for the socket out let and complete with connections, testing and commissioning etc. as required.	78.00	Nos			0.00	INR Zero Only
1.14	Supplying and fixing following rating, four pole, 415 V, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required. 63A.	20.00	Nos			0.00	INR Zero Only
1.15	Supplying and fixing 3 pin, 5 amp ceiling rose on the existing junction box/ wooden block including connection etc. as required.	600.00	Nos			0.00	INR Zero Only
1.16	Supplying and fixing brass batten /angle holder including connection etc. as required.	200.00	Nos			0.00	INR Zero Only
1.17	Providing and fixing following rating and breaking capacity and pole MCCB with thermo magnetic release and terminal spreaders in existing cubicle panel board including drilling holes in cubicle panel, making connections, etc. as required. 100A , 30KA, FPMCCB	7.00	Nos			0.00	INR Zero Only
1.18	Supplying, installation, testing and commissioning of following capacity TPN tap off box made of 1.6 mm thick sheet steel enclosure duly painted with power coating on existing rising mains complete with TPN disconnecter FUS and HRC fuses, connections, earthing etc as required. 63 amp TPN	10.00	Nos			0.00	INR Zero Only
1.19	Supplying, installation, testing and commissioning of following capacity TPN tap off box made of 1.6 mm thick sheet steel enclosure duly painted with power coating on existing rising mains complete with TPN disconnecter FUS and HRC fuses, connections, earthing etc as required. 100 amp TPN	5.00	Nos			0.00	INR Zero Only

1.2	Supplying, installation, testing and commissioning of following capacity TPN tap off box made of 1.6 mm thick sheet steel enclosure duly painted with power coating on existing rising mains complete with TPN disconnecter FUS and HRC fuses, connections, earthing etc as required. 200 amp TPN	4.00	Nos			0.00	INR Zero Only
2.01	Supplying, installation, testing and commissioning of following capacity TPN tap off box made of 1.6 mm thick sheet steel enclosure duly painted with power coating on existing rising mains complete with TPN disconnecter FUS and HRC fuses, connections, earthing etc as required. 400 amp TPN	1.00	No			0.00	INR Zero Only
2.02	Earthing with copper earth plate 600 mm x 600mm x 3 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/coke and salt as required.	6.00	Set			0.00	INR Zero Only
2.03	Supplying and fixing metal box of following sizes (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including painting etc. as required. 100mm x 100mm x 60 mm deep.	40.00	Nos			0.00	INR Zero Only
2.04	Supplying and fixing metal box of following sizes (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including painting etc. as required. 180 mm x 100 mm x 60 mm deep.	30.00	Nos			0.00	INR Zero Only
2.05	Supplying and fixing metal box of following sizes (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including painting etc. as required. 200 mm x 150 mm x 60 mm deep.	25.00	Nos			0.00	INR Zero Only
2.06	Supplying and fixing metal box of following sizes (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including painting etc. as required. 200 mm x 250 mm x 60 mm deep.	20.00	Nos			0.00	INR Zero Only
2.07	Providing and fixing 25 mm x 5 mm copper strip on surface or in recess for connection etc. as required.	60.00	Mtrs			0.00	INR Zero Only
2.08	Providing and fixing 4.00 mm copper wire on surface or in recess for loop earthing etc. as required.	120.00	Mtrs			0.00	INR Zero Only
2.09	Providing 15mm thick cement plaster of mix 1:4 (1 cement : 4 fine sand ) at all levels.	450.00	sqm			0.00	INR Zero Only
2.1	Providing and applying plaster of Paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete.	450.00	sqm			0.00	INR Zero Only
2.11	Providing and fixing of 2x2 recessed LED Panel light fitting. (36 watt).	32.00	Nos			0.00	INR Zero Only
2.12	Providing and fixing of LED Luminaire 20 watt (Surface).	150.00	Nos			0.00	INR Zero Only
5	<b>Total impact of GST for the purpose of CTC</b>	1.000	Nos		0.00	0.00	INR Zero Only
<b>Total in Figures</b>						<b>0.00</b>	INR Zero Only
<b>Quoted Rate in Words</b>	<b>INR Zero Only</b>						