

Validate

Print

Help

## Percentage BoQ

Tender Inviting Authority: PE (Civil) G M Unit, Bn K Area

Name of Work: Repair and Maintenance of Garrage at River dale colony under GM Unit of BnK Area.

	<b>Category of Services (To Be Selected by Department)</b>	<b>Category of Bidder(To Be Selected by Bidder)</b>	<b>To Be Entered by Department</b>		
<b>ITC Not Available</b>	<b>Works Contract</b>	<b>Bidder's Status (Mandatory)</b>	<b>Rate of GST (in %)</b>	<b>GST to be Paid By Bidder (in Rs.)</b>	<b>GST to be Paid By CIL/Subsidiary (in Rs.)</b>
<b>Name of the Bidder/ Bidding Firm / Company :</b>		<b>Select</b>	<b>18.00</b>	<b>0.00</b>	<b>0.00</b>

## PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.All kinds of soil.	5.350	cum	188.45	1008.21	INR One Thousand &Eight and Paise Twenty One Only
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	4.500	cum	6490.90	29209.05	INR Twenty Nine Thousand Two Hundred & Nine and Paise Five Only
3	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20 mm nominal size stone aggregate	84.000	sqm	452.50	38010.00	INR Thirty Eight Thousand &Ten Only
4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6(1 cement :6 coarse sand)	5.030	cum	5322.15	26770.41	INR Twenty Six Thousand Seven Hundred & Seventy and Paise Forty One Only
5	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6(1 cement : 6 coarse sand)	9.710	cum	6494.75	63064.02	INR Sixty Three Thousand &Sixty Four and Paise Two Only
6	12 mm cement plaster of mix: 1:6(1 cement: 6 fine sand)	351.980	sqm	217.70	76626.05	INR Seventy Six Thousand Six Hundred & Twenty Six and Paise Five Only
7	Providing reinforced by organic fibres and/or inorganic synthetic fibres cement 6 mm thick corrugated sheets (as per IS: 14871) roofing up to any pitch and fixing with polymer coated J or L hooks, bolts and nuts 8 mm dia. G.I. plain and bitumen washers or with self drilling fastener and EPDM washers etc. complete (excluding the cost of purlins, rafters and trusses), including cutting sheets to size and shape wherever required.	99.820	sqm	389.10	38839.96	INR Thirty Eight Thousand Eight Hundred & Thirty Nine and Paise Ninety Six Only
8	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	148.500	KG	77.95	11575.58	INR Eleven Thousand Five Hundred & Seventy Five and Paise Fifty Eight Only
9	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	1008.000	KG	92.55	93290.40	INR Ninety Three Thousand Two Hundred & Ninety and Paise Forty Only
10	Finishing walls with water proofing cement paint of required shade: New work (Two or more coats applied @ 3.84 kg/10 sqm)	351.980	sqm	74.70	26292.91	INR Twenty Six Thousand Two Hundred & Ninety Two and Paise Ninety One Only
11	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :	56.700	sqm	99.90	5664.33	INR Five Thousand Six Hundred & Sixty Four and Paise Thirty Three Only
12	<b>Total impact of GST for the purpose of CTC</b>	1.000	Nos	<b>0.00</b>	<b>0.00</b>	INR Zero Only
<b>Total in Figures</b>					<b>410350.91</b>	INR Four Lakh Ten Thousand Three Hundred & Fifty and Paise Ninety One Only
<b>Quoted Rate in Figures</b>			<b>Select</b>		<b>0.00</b>	INR Zero Only
<b>Quoted Rate in Words</b>						<b>INR Zero Only</b>