

Validate

Print

Help

Percentage BoQ

Tender Inviting Authority: PE (Civil) G M Unit, Bn K Area

Name of Work: Repair of culvert near Shiv Mandir Ghutiyatand under GM Unit BnK Area.

	Category of Services (To Be Selected by Department)	Category of Bidder(To Be Selected by Bidder)	To Be Entered by Department		
ITC Not Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)
Name of the Bidder/ Bidding Firm / Company :		Select	18.00	0.00	0.00

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.	23.100	CUM	205.80	4753.98	INR Four Thousand Seven Hundred & Fifty Three and Paise Ninety Eight Only
2	Supplying and filling in plinth with Jamuna sand under floors, including watering, ramming, consolidating and dressing complete.	0.500	CUM	1438.10	719.05	INR Seven Hundred & Nineteen and Paise Five Only
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	1.000	CUM	6773.95	6773.95	INR Six Thousand Seven Hundred & Seventy Three and Paise Ninety Five Only
4	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :1:1.5:3(1 cement: 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	6.900	CUM	8343.45	57569.81	INR Fifty Seven Thousand Five Hundred & Sixty Nine and Paise Eighty One Only
5	Centering and shuttering including strutting, propping etc. and form for :Foundations, footings, bases of columns, etc. for mass concrete	2.720	SQM	277.90	755.89	INR Seven Hundred & Fifty Five and Paise Eighty Nine Only
6	Centering and shuttering including strutting, propping etc. and form for Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	23.320	SQM	562.75	13123.33	INR Thirteen Thousand One Hundred & Twenty Three and Paise Thirty Three Only
7	Centering and shuttering including strutting, propping etc. and removal of form for :Suspended floors, roofs, landings, balconies and access platform	8.720	SQM	630.00	5493.60	INR Five Thousand Four Hundred & Ninety Three and Paise Sixty Only
8	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.Thermo-Mechanically Treated bars	621.000	KG	105.60	65577.60	INR Sixty Five Thousand Five Hundred & Seventy Seven and Paise Sixty Only
9	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	60.000	CUM	118.65	7119.00	INR Seven Thousand One Hundred & Nineteen Only
10	Total impact of GST for the purpose of CTC	1.000	Nos	0.00	0.00	INR Zero Only
Total in Figures					161886.20	INR One Lakh Sixty One Thousand Eight Hundred & Eighty Six and Paise Twenty Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words						INR Zero Only